

**A STUDY OF OCCUPANCY-BASED SMART
BUILDING CONTROLS IN COMMERCIAL
BUILDINGS- SUPPORTING DOCUMENT**

Chul Kim, Ph.D.

September 2023



ENERGY SYSTEMS LABORATORY
TEXAS A&M ENGINEERING EXPERIMENT STATION

DISCLAIMER

This report is provided by the Texas Engineering Experiment Station (TEES) as required under Section 388.003 (e) of the Texas Health and Safety Code and is distributed for purposes of public information. The information provided in this report is intended to be the best available information at the time of publication. TEES makes no claim or warranty, express or implied, that the report or data herein is necessarily error-free. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not constitute or imply its endorsement, recommendation, or favoring by the Energy Systems Laboratory or any of its employees. The views and opinions of authors expressed herein do not necessarily state or reflect those of the Texas Engineering Experiment Station or the Energy Systems Laboratory

EXECUTIVE SUMMARY

These days, building energy performance simulation (BEPS) is widely used to predict building energy use in the process of building designs. Thermal zones in BEPS impacts building system efficiency and (i.e., HVAC, lighting, and equipment systems) and performance as a basic unit to control indoor space. For the modeling of thermal zones, conventional design methods have been used to determine thermal zone designs in practice. However, the advances of building technology and control require more sophisticated zoning methods in BEPS to be wise in controls and reduce energy waste.

In previous research, many studies discussed the importance of thermal zoning methods. However, the details of the impact of thermal zoning were not fully investigated, especially in different HVAC systems, occupant usage intensities, and climates. These factors would significantly affect the energy efficiency in building operations. Therefore, Kim (2020) explored the impact of thermal zoning methods under different buildings and climate conditions (i.e., hot-humid, and cold-humid) to support proper thermal zoning determination.

Therefore, this report contains detailed information of the reference simulation models used in Kim (2020), including thermal zoning methods (i.e., single-zone, five-zone, and detailed zone models), HVAC systems (i.e., Packaged Single Zone (PSZ) system, Packaged Variable Air Volume (PVAV) system), and Occupant usage Intensity (i.e., : 100%-for-24hrs / 0%-for-24hrs / ASHRAE Standard 90.1-2016 schedule).

The reference models (i.e., single-zone, five-zone models) for DOE-2.1e were developed based on the USDOE prototype parameters (PNNL and U.S.DOE 2019), which were used to compare the impact on energy use due to thermal zone models. The detailed zone models were modeled based on the Oak Ridge National Laboratory (ORNL) research (Im et al. 2019; Im and New 2018) to represent a detailed space programs and usage in an office building.

The four reference simulation models are described in Section 2 and Appendix A for the DOE-2.1e program, including the BDL descriptions and simulation boundary and input conditions.

TABLE OF CONTENTS

EXECUTIVE SUMMARY	3
TABLE OF CONTENTS	4
LIST OF TABLES	5
1 INTRODUCTION	6
2 SIMULATION DESCRIPTION.....	7
2.1 DOE-2.1E Simulation Cases for the Small Office Building	7
2.2 Houston, TX: Thermal Zoning Models.....	8
2.2.1 Reference Model 1: Five-Zone Model in Houston, TX (PSZ System).....	8
2.2.2 Reference Model 2: Five-Zone Model in Houston, TX (PVAV System).....	21
2.3 Chicago, IL: Thermal Zoning Models.....	33
2.3.1 Reference Model 1: Single-Zone Model in Chicago, IL (PSZ System)	33
2.3.2 Reference Model 2: Five-Zone Model in Chicago, IL (PVAV System)	45
3 REFERENCE.....	57
Appendix A: Simulation Information.....	58

LIST OF TABLES

Table 2-1 Simulation Cases used for the analysis	7
Table A-1 Summary of Small Office Model Construction.....	58
Table A-2 Houston (2A): Small Office Model Material Layers.....	58
Table A-3 Chicago (5A): Small Office Model Material Layers.....	58
Table A-4 Average Monthly Ground Temperature in DOE-2.1e and EnergyPlus.....	59
Table A-5 Internal Heat Gain Inputs in DOE-2.1e and EnergyPlus Simulation Tests.....	59

1 INTRODUCTION

In building energy performance simulations (BEPS), thermal zoning determines which parts of a building are controlled by a single thermostat (i.e., heating, cooling, lighting, and ventilation). Therefore, proper thermal zoning impacts building energy use and efficiency. This report provides detailed information to support the previous study conducted by Kim (2020). In this report, details about simulation cases are included for different HVAC systems and occupant usage intensities in hot-humid and cold-humid climates (i.e., Houston, TX, and Chicago, IL), including:

- Thermal zoning method: single-zone, five-zone, and detailed zone model
- HVAC system type: Packaged Single Zone (PSZ) system, Packaged Variable Air Volume (PVAV) system
- Occupant usage Intensity: 100%-for-24hrs / 0%-for-24hrs / ASHRAE Standard 90.1-2016 schedules

In this study, the USDOE prototype parameters (PNNL and U.S.DOE 2019) were adopted and modified to compare the energy performance depending on thermal zone designs. The detailed zone models were developed based on the Oak Ridge National Laboratory (ORNL) research (Im et al. 2019; Im and New 2018) to represent a detailed office building.

In this report, four reference simulation models are presented for the DOE-2.1e program, including for the BDL descriptions in Section 2 to provide detailed information of thermal zoning models.

2 SIMULATION DESCRIPTION

2.1 DOE-2.1E Simulation Cases for the Small Office Building

In this study, three types of thermal zoning models were analyzed using the PSZ and PVAV systems. These models were operated using three occupant usage intensities to control the HVAC, lighting, and equipment systems. Table 1 shows the simulation combinations for the small office building in the DOE-2.1E program.

Table 2-1 Simulation Cases used for the analysis

Location	Zoning Model	HVAC Type	Modeling Schedule Type (Weekdays)					Avg. WWR
			Occupancy	Lighting	Equipment	Set-point	Set-back	
Houston TX	• Single- zone	PSZ	1) 90.1-2016	1) 90.1-2016	1) 90.1-2016	H: 70°F	H: 60°F	21%
			2) 100%24hrs	2) 100%24hrs	2) 100%24hrs	C: 75°F	C: 85°F	
			3) 0% 24 hrs	3) 0% 24 hrs	3) 0% 24 hrs			
	• Detailed-zone	PVAV	1) 90.1-2016	1) 90.1-2016	1) 90.1-2016	H: 70°F	H: 60°F	21%
			2) 100%24hrs	2) 100%24hrs	2) 100%24hrs	C: 75°F	C: 85°F	
			3) 0% 24 hrs	3) 0% 24 hrs	3) 0% 24 hrs			
Chicago IL	• Single- zone	PSZ	1) 90.1-2016	1) 90.1-2016	1) 90.1-2016	H: 70°F	H: 60°F	21%
			2) 100%24hrs	2) 100%24hrs	2) 100%24hrs	C: 75°F	C: 85°F	
			3) 0% 24 hrs	3) 0% 24 hrs	3) 0% 24 hrs			
	• Detailed-zone	PVAV	1) 90.1-2016	1) 90.1-2016	1) 90.1-2016	H: 70°F	H: 60°F	21%
			2) 100%24hrs	2) 100%24hrs	2) 100%24hrs	C: 75°F	C: 85°F	
			3) 0% 24 hrs	3) 0% 24 hrs	3) 0% 24 hrs			

* Weekend schedules set to minimum operating rates in the simulation schedules (i.e., occupancy=0.0; lighting=0.18; equipment=0.20; infiltration=off; ventilation fan=0.0; set-temperature: heating 60°F, cooling 85°F) (PNNL & U.S.DOE, 2019b).

* Window-to-wall (WWR) ratio in the small office models was 21% on average. Window fraction was 24.4% for the South and 19.8% for the other three orientations (e.g., east, west, north).

In this section, among hundreds simulation combinations, the DOE-2 BDL input files for five-zone models using the PSZ and PVAV systems in Houston, TX, and Chicago, IL are selected and listed to provide more modeling information in the DOE-2.1e program.

- Reference Model 1: Five-Zone Model in Houston, TX (PSZ System)
- Reference Model 2: Five-Zone Model in Houston, TX (PVAV System)
- Reference Model 3: Five-Zone Model in Chicago, IL (PSZ System)
- Reference Model 4: Five-Zone Model in Chicago, IL (PVAV System)

2.2 Houston, TX: Thermal Zoning Models

2.2.1 Reference Model 1: Five-Zone Model in Houston, TX (PSZ System)

In this section, the DOE-2 BDL input file for the PSZ system for “Case 1: Single-Zone Model in Houston, TX” is described. The DOE-2 reference model is based on the U.S.DOE commercial prototype models with five zones (PNNL and U.S.DOE 2019).

```

1  $===== SIMULATION ZONING =====
2
3  INPUT LOADS ..
4
5  TITLE          LINE-1 *SAMPLE PROVIDED BY PROF.JEFF HABERL*
6                LINE-2 *HOUSTON, TX, CLIMATE ZONE 2A*
7                LINE-3 *ASHRAE 90.1-2016 REQUIREMENTS SATISFIED*
8                LINE-4 *STUDY FOR BUILDING OCCUPANCY PROFILE ANALYSIS* ..
9
10             RUN-PERIOD      JAN 1 2019 THRU DEC 31 2019 ..
11
12             ABORT            ERRORS ..
13             DIAGNOSTIC      WARNINGS ..
14             LOADS-REPORT    SUMMARY = (ALL-SUMMARY)
15                             REPORT-FREQUENCY = HOURLY
16                             HOURLY-DATA-SAVE = FORMATTED
17                             VERIFICATION = (ALL-VERIFICATION) ..
18
19             BUILDING-LOCATION LATITUDE=30.0
20                             LONGITUDE=95.37
21                             GROUND-T = (69.314, 69.224, 69.368, 69.512,
22                             69.692,73.634,74.3, 74.444, 74.48, 70.448,
23                             69.818, 69.458)
24                             DAYLIGHT-SAVINGS =
25                             NO
26                             ALTITUDE=95.14
27                             TIME-ZONE=6
28                             AZIMUTH=0.0 ..
29
30  $ BUILDING DESCRIPTION
31
32  $===== BUILDING CONSTRUCTION =====
33
34  $ CONSTRUCTION AND GLASS-TYPES
35
36  $ MATERIAL PROPERTY (IF UNITS)
37  $ ALL VALUES CONVERTED FROM SI UNITS IN PNNL SMALL OFFICE MODEL FOR 90.1-2016
38  $ ROOF AND CEILING PROPERTY
39  ROOF_BUIL      = MAT          THICKNESS = 0.03116798
40                                     CONDUCTIVITY = 0.092446272
41                                     DENSITY = 69.9193264
42                                     SPECIFIC-HEAT = 0.348715014 ..
43
44  ROOF_INS_1    = MAT          RESISTANCE = 24.52377767 ..
45
46  ROOF_INS_2    = MAT          RESISTANCE = 35.40275850 ..
47
48  ROOF_SUR_1    = MAT          THICKNESS = 0.002624672
49                                     CONDUCTIVITY = 26.16229498
50                                     DENSITY = 488.4364373
51                                     SPECIFIC-HEAT = 0.11942295 ..
52
53  CEIL_MAT      = MAT          THICKNESS = 0.041666668
54                                     CONDUCTIVITY = 0.032933984
55                                     DENSITY = 17.97925536
56                                     SPECIFIC-HEAT = 0.31981466 ..
57
58  ROOF_ASPTH    = MAT          THICKNESS = 0.010498688
59                                     CONDUCTIVITY = 0.023111568
60                                     DENSITY = 69.9193264
61                                     SPECIFIC-HEAT = 0.300945834 ..
62
63  ROOF_WOOD     = MAT          THICKNESS = 0.052165356
64                                     CONDUCTIVITY = 0.069334704
65                                     DENSITY = 33.96081568
66                                     SPECIFIC-HEAT = 0.289003539 ..
67
68
69
70  $ SLAB PROPERTY
71  SLAB_CONC200 = MAT          THICKNESS = 0.66666668
72                                     CONDUCTIVITY = 1.334693052

```



```

73          DENSITY = 144.9577463
74          SPECIFIC-HEAT = 0.198719789 ..
75
76  SLAB_CONC100 = MAT          THICKNESS = 0.333333344
77          CONDUCTIVITY = 1.334693052
78          DENSITY = 144.9577463
79          SPECIFIC-HEAT = 0.198719789 ..
80
81  SLAB_CARP      = MAT          RESISTANCE = 1.22923033 ..
82
83
84  $ WALL PROPERTY
85  WALL_STU      = MAT          THICKNESS = 0.083333336
86          CONDUCTIVITY = 0.416008224
87          DENSITY = 115.8663123
88          SPECIFIC-HEAT = 0.200630556 ..
89
90  WALL_GYP1     = MAT          THICKNESS = 0.052165356
91          CONDUCTIVITY = 0.092446272
92          DENSITY = 49.942376
93          SPECIFIC-HEAT = 0.260342031 ..
94
95  WALL_GYP2     = MAT          THICKNESS = 0.041666668
96          CONDUCTIVITY = 0.092446272
97          DENSITY = 49.942376
98          SPECIFIC-HEAT = 0.260342031 ..
99
100 WALL_INS_1    = MAT          RESISTANCE = 9.72589032 ..
101
102 WALL_INS_2    = MAT          RESISTANCE = 9.05708346 ..
103
104
105  $ WINDOW PROPERTY
106  WIN_GLS3     = GLASS-TYPE    GLASS-CONDUCTANCE = 0.6535
107          VIS-TRANS = 0.312
108          SHADING-COEF =
109          0.286206897
110          PANES = 2 ..
111
112  DOOR1        = GLASS-TYPE    GLASS-CONDUCTANCE = 0.370
113          SHADING-COEF = 0.7 ..
114
115  AIR-LAYER    = CONSTRUCTION  U = 1.11 ..
116
117
118  $ MATERIAL LAYERS
119  ATTIC-R1    =LAYERS =MAT=(AR02,PW04) ..
120
121  ATTIC-R2    =LAYERS =MAT=(PW04) ..
122
123  ROOF 1     =LAYERS =MAT=(ROOF INS 2,GP02) ..
124  EX_SLAB_1  =LAYERS =MAT=(SLAB_CONC200,CP02) ..
125  EX_WALL_1  =LAYERS =MAT=(SC01,GP02,WALL_INS_2,GP02) ..
126  IN_WALL_1  =LAYERS =MAT=(GP01,GP01) ..
127  IN_SLAB_1  =LAYERS =MAT=(SLAB_CONC100,CP02) ..
128  CEIL_MAT1  =LAYERS =MAT=(AC02,GP01) ..
129
130
131  $ MATERIAL CONSTRUCTION
132  EXT_SLAB    =CONSTRUCTION    LAYERS = EX_SLAB 1
133          ABSORPTANCE = 0.7 ..
134  NONRES_EXT_WALL =CONSTRUCTION LAYERS = EX_WALL 1
135          ABSORPTANCE = 0.7 ..
136  INT_WALL    =CONSTRUCTION    LAYERS = IN_WALL 1
137          ABSORPTANCE = 0.7 ..
138  CEIL_MAT2   =CONSTRUCTION    LAYERS = ROOF 1
139          ABSORPTANCE = 0.7 ..
140  ATTIC-ROOF  =CONSTRUCTION    LAYERS = ATTIC-R1
141          ABSORPTANCE = 0.7 ..
142  ATTIC-SOFFIT =CONSTRUCTION    LAYERS = ATTIC-R2
143          ABSORPTANCE = 0.7 ..
144  DOOR2       =CONSTRUCTION    U = 1.2139351092

```

```

145                                     ABSORPTANCE = 0.7 ..
146
147 $ OCCUPANCY SCHEDULE
148 OC-1          =DAY-SCHEDULE          (1,6) (0.0)
149              (7) (0.11)
150              (8) (0.21)
151              (9,12) (1.0)
152              (13) (0.53)
153              (14,17) (1.0)
154              (18) (0.32)
155              (19,22) (0.11)
156              (23) (0.05)
157              (24) (0.0) ..
158
159 OC-2          =DAY-SCHEDULE          (1,6) (0.0)
160              (7,8) (0.1)
161              (9,12) (0.3)
162              (13,17) (0.1)
163              (18,19) (0.05)
164              (20,24) (0.0) ..
165
166 OC-3          =DAY-SCHEDULE          (1,6) (0.0)
167              (7,18) (0.05)
168              (19,24) (0.0) ..
169
170 OC-4          =DAY-SCHEDULE          (1,24) (0.0) ..
171 OC-5          =DAY-SCHEDULE          (1,24) (1.0) ..
172
173
174 OC-WEEK       =WEEK-SCHEDULE          (WD) OC-1 (SAT) OC-4 (SUN) OC-4 (HOL) OC-4 ..
175 OC-WEEK2      =WEEK-SCHEDULE          (WD) OC-4 (SAT) OC-4 (SUN) OC-4 (HOL) OC-4 ..
176 OC-WEEK3      =WEEK-SCHEDULE          (WD) OC-5 (SAT) OC-5 (SUN) OC-5 (HOL) OC-5 ..
177
178 OCCUPY-1      =SCHEDULE                THRU DEC 31 OC-WEEK ..
179 OCCUPY-2      =SCHEDULE                THRU DEC 31 OC-WEEK2 ..
180 OCCUPY-3      =SCHEDULE                THRU DEC 31 OC-WEEK3 ..
181
182
183
184 $ LIGHTING SCHEDULE
185
186 LT-1          =DAY-SCHEDULE          (1,5) (0.18)
187              (6,7) (0.23)
188              (8) (0.42)
189              (9,12) (0.9)
190              (13) (0.8)
191              (14,17) (0.9)
192              (18) (0.61)
193              (19,20) (0.42)
194              (21,22) (0.32)
195              (23) (0.23)
196              (24) (0.18) ..
197
198 LT-2          =DAY-SCHEDULE          (1,6) (0.05)
199              (7,8) (0.1)
200              (9,12) (0.3)
201              (13,17) (0.15)
202              (18,24) (0.05) ..
203
204 LT-3          =DAY-SCHEDULE          (1,24) (0.18) ..
205 LT-4          =DAY-SCHEDULE          (1,24) (0.0) ..
206 LT-5          =DAY-SCHEDULE          (1,24) (1.0) ..
207
208
209 LT-WEEK       =WEEK-SCHEDULE          (WD) LT-1 (SAT) LT-3 (SUN) LT-3 (HOL) LT-3 ..
210 LT-WEEK2      =WEEK-SCHEDULE          (WD) LT-3 (SAT) LT-3 (SUN) LT-3 (HOL) LT-3 ..
211 LT-WEEK3      =WEEK-SCHEDULE          (WD) LT-5 (SAT) LT-5 (SUN) LT-5 (HOL) LT-5 ..
212
213
214 LIGHTS-1      =SCHEDULE                THRU DEC 31 LT-WEEK ..
215 LIGHTS-2      =SCHEDULE                THRU DEC 31 LT-WEEK2 ..
216 LIGHTS-3      =SCHEDULE                THRU DEC 31 LT-WEEK3 ..
217

```

```

218
219
220 $ OFFICE EQUIPMENT SCHEDULE
221 EQ-1      =DAY-SCHEDULE      (1,5) (0.5)
222          (6,12) (1.0)
223          (13) (0.94)
224          (14,17) (1.0)
225          (18) (0.5)
226          (19,24) (0.2) ..
227
228
229 EQ-2      =DAY-SCHEDULE      (1,6) (0.3)
230          (7,8) (0.4)
231          (9,12) (0.5)
232          (13,17) (0.35)
233          (18,24) (0.3) ..
234
235 EQ-3      =DAY-SCHEDULE      (1,24) (0.2) ..
236 EQ-4      =DAY-SCHEDULE      (1,24) (0.0) ..
237 EQ-5      =DAY-SCHEDULE      (1,24) (1.0) ..
238
239
240 EQ-WEEK   =WEEK-SCHEDULE      (WD) EQ-1 (SAT) EQ-3 (SUN) EQ-3 (HOL) EQ-3 ..
241 EQ-WEEK2  =WEEK-SCHEDULE      (WD) EQ-3 (SAT) EQ-3 (SUN) EQ-3 (HOL) EQ-3 ..
242 EQ-WEEK3  =WEEK-SCHEDULE      (WD) EQ-5 (SAT) EQ-5 (SUN) EQ-5 (HOL) EQ-5 ..
243 EQ-WEEK4  =WEEK-SCHEDULE      (WD) EQ-0 (SAT) EQ-4 (SUN) EQ-4 (HOL) EQ-3 ..
244 EQ-WEEK5  =WEEK-SCHEDULE      (WD) EQ-6 (SAT) EQ-7 (SUN) EQ-7 (HOL) EQ-7 ..
245
246
247 EQUIP-1   =SCHEDULE           THRU DEC 31 EQ-WEEK ..
248 EQUIP-2   =SCHEDULE           THRU DEC 31 EQ-WEEK2 ..
249 EQUIP-3   =SCHEDULE           THRU DEC 31 EQ-WEEK3 ..
250
251
252 $ INFILTRATION SCHEDULE
253 IF-1      =DAY-SCHEDULE      (1,6) (1.0)
254          (7,19) (0.25)
255          (20,24) (1.0) ..
256
257 IF-2      =DAY-SCHEDULE      (1,7) (1.0)
258          (8,18) (0.25)
259          (19,24) (1.0) ..
260
261 IF-3      =DAY-SCHEDULE      (1,24) (0.0) ..
262 IF-4      =DAY-SCHEDULE      (1,24) (1.0) ..
263 IF-5      =DAY-SCHEDULE      (1,24) (0.25) ..
264
265
266 IF-WEEK   =WEEK-SCHEDULE      (WD) IF-1 (SAT) IF-2 (SUN) IF-4 (HOL) IF-4 ..
267 IF-WEEK2  =WEEK-SCHEDULE      (WD) IF-4 (SAT) IF-4 (SUN) IF-4 (HOL) IF-4 ..
268 IF-WEEK3  =WEEK-SCHEDULE      (WD) IF-5 (SAT) IF-5 (SUN) IF-5 (HOL) IF-5 ..
269
270
271 INFIL-SCH =SCHEDULE           THRU DEC 31 IF-WEEK ..
272 INFIL-SCH2 =SCHEDULE           THRU DEC 31 IF-WEEK2 ..
273 INFIL-SCH3 =SCHEDULE           THRU DEC 31 IF-WEEK3 ..
274
275
276
277 $===== SPACE DEFAULTS & DESCRIPTION =====
278
279
280 $ SET DEFAULT VALUE
281
282         SET-DEFAULT FOR SPACE FLOOR-WEIGHT = 0 ..
283         SET-DEFAULT FOR WINDOW HEIGHT=5.0
284                 GLASS-TYPE=WIN GLS3 Y=1 ..
285         SET-DEFAULT FOR EXTERIOR-WALL CONSTRUCTION=NONRES_EXT_WALL ..
286
287
288 $ GENERAL SPACE DEFINITION
289
290 OFFICE     =SPACE-CONDITIONS  PEOPLE-SCHEDULE      =OCCUPY-1

```

```

291          NUMBER-OF-PEOPLE      =31
292          PEOPLE-HEAT-GAIN       =450
293          LIGHTING-SCHEDULE      =LIGHTS-1
294          LIGHTING-W/SQFT        = 0.79
295          EQUIP-SCHEDULE         = EQUIP-1
296          EQUIPMENT-W/SQFT       = 0.63
297          INF-METHOD            = AIR-CHANGE
298          AIR-CHANGES/HR        = 0.0
299          INF-SCHEDULE            =INFIL-SCH2 ..
300
301
302          $ SPECIFIC SPACE DETAILS
303
304          $ ATTIC
305          ATTIC-SC      = SPACE-CONDITIONS
306                      ZONE-TYPE = UNCONDITIONED
307                      FLOOR-WEIGHT = 0 ..          $ CUSTOM WEITING FACTOR
308                                                    $ SEE p. III.141+
309          ATTIC      = SPACE      S-C = ATTIC-SC  AREA = 6113.686  VOLUME = 24533.31
310                      X = 0  Y = 0  Z = 0  AZ = 0 ..
311          N-ROOF = POLYGON
312                      (92.81,62.53) (-1.97,62.53) (30.28,32.03) (60.56,32.03) ..
313          S-ROOF = POLYGON
314                      (-1.97,-1.97) (92.81,-1.97) (60.56,32.03) (30.28,32.03) ..
315          E-GABLE = POLYGON
316                      (0,0) (64.5,0) (32.25,34) ..
317          W-GABLE = POLYGON
318                      (-1.97,62.53,10) (-1.97,-1.97,10) (30.28,30.28,20.77) ..
319
320
321          $ ROOF RAISED
322          N-ROOF-EXT = ROOF          CONSTRUCTION = ATTIC-ROOF
323                                      POLYGON = S-ROOF
324                                      TILT =18.5, AZ = 0,
325                                      X= 90.84 Y = 60.56 Z = 10.0 ..
326
327          S-ROOF-EXT = ROOF          CONSTRUCTION = ATTIC-ROOF
328                                      POLYGON = S-ROOF
329                                      TILT =18.5, AZ = 180, Z = 10.0 ..
330
331          E-GABLE-EXT = ROOF         CONSTRUCTION = ATTIC-ROOF
332                                      POLYGON = E-GABLE
333                                      TILT =18.2, AZ = 90
334                                      X = 92.81 Y = -1.97 Z = 10.0 ..
335
336          W-GABLE-EXT = ROOF         CONSTRUCTION = ATTIC-ROOF
337                                      POLYGON = E-GABLE
338                                      TILT =18.2, AZ = 270
339                                      X = -1.97 Y = 62.53 Z = 10.0 ..
340
341
342          N-ROOF-SOFFIT = BUILDING-SHADE HEIGHT = 1.97  WIDTH = 94.78
343                                      X=-1.97  Y=60.6  Z=10
344                                      TRANSMITTANCE = 0.0
345                                      AZIMUTH = 180  TILT = 180 ..
346
347          S-ROOF-SOFFIT = BUILDING-SHADE HEIGHT = 1.97  WIDTH =
348          94.78
349                                      X=-1.97  Y=0  Z=10
350                                      TRANSMITTANCE = 0.0
351                                      AZIMUTH = 180  TILT = 180 ..
352
353          E-ROOF-SOFFIT = BUILDING-SHADE HEIGHT = 1.97  WIDTH =
354          60.56
355                                      X=90.85  Y=0  Z=10
356                                      TRANSMITTANCE = 0.0
357                                      AZIMUTH = 90  TILT = 180 ..
358
359          W-ROOF-SOFFIT = BUILDING-SHADE HEIGHT = 1.97  WIDTH =
360          60.56
361                                      X=0  Y=0  Z=10
362                                      TRANSMITTANCE = 0.0
363                                      AZIMUTH = 90  TILT = 180 ..

```

```

361
362 SPACE1-1      =SPACE      SPACE-CONDITIONS = OFFICE
363                                     AREA = 1221.28925 VOLUME = 12221.4264
364                                     NUMBER-OF-PEOPLE = 7 ..
365 FRONT-1      =EXTERIOR-WALL  HEIGHT = 10 WIDTH = 90.8
366                                     X=0 Y=0 Z=0 AZIMUTH = 180 ..
367
368 WF-1         =WINDOW      WIDTH = 6 X = 4.56 Y = 2.95 ..
369 WF-2         =WINDOW      WIDTH = 6 X = 19.72 Y = 2.95 ..
370 WF-3         =WINDOW      WIDTH = 6 X = 34.84 Y = 2.95 ..
371 WF-4         =WINDOW      WIDTH = 6 X = 50.00 Y = 2.95 ..
372 WF-5         =WINDOW      WIDTH = 6 X = 65.12 Y = 2.95 ..
373 WF-6         =WINDOW      WIDTH = 6 X = 80.28 Y = 2.95 ..
374 DF-1         =WINDOW      WIDTH = 6 HEIGHT = 7
375                                     X = 42.42 Y = 0
376                                     GLASS-TYPE=WIN_GLS3 ..
377
378 C1-1         =INTERIOR-WALL  AREA = 1221.28925 NEXT-TO ATTIC
379                                     CONSTRUCTION = CEIL_MAT2 ..
380
381 F1-1         =UNDERGROUND-FLOOR  AREA = 1221.28925 CONSTRUCTION = EXT_SLAB ..
382
383 SB12         =INTERIOR-WALL  AREA=231.931 NEXT-TO SPACE2-1
384                                     CONSTRUCTION = INT_WALL ..
385
386 SB14         =INTERIOR-WALL  LIKE SB12 NEXT-TO SPACE4-1 ..
387 SB15         =INTERIOR-WALL  AREA 580 NEXT-TO SPACES5-1
388                                     CONSTRUCTION = INT_WALL ..
389
390 SPACE2-1     =SPACE      SPACE-CONDITIONS = OFFICE
391                                     AREA = 724.4845 VOLUME = 7249.7832
392                                     NUMBER-OF-PEOPLE = 4 ..
393
394 RIGHT-1     =EXTERIOR-WALL  HEIGHT = 10 WIDTH = 60.5
395                                     X=90.8 Y=0 Z=0 AZIMUTH = 90 ..
396
397 WR-1         =WINDOW      WIDTH = 6 X = 4.56 Y = 2.95 ..
398 WR-2         =WINDOW      WIDTH = 6 X = 19.72 Y = 2.95 ..
399 WR-3         =WINDOW      WIDTH = 6 X = 34.84 Y = 2.95 ..
400 WR-4         =WINDOW      WIDTH = 6 X = 50.00 Y = 2.95 ..
401
402 C2-1         =INTERIOR-WALL  AREA = 724.4845 NEXT-TO ATTIC
403                                     CONSTRUCTION = CEIL_MAT2 ..
404
405 F2-1         =UNDERGROUND-FLOOR  AREA = 724.4845 CONSTRUCTION = EXT_SLAB ..
406
407 SB23         =INTERIOR-WALL  AREA = 231.931 NEXT-TO SPACE3-1
408                                     CONSTRUCTION = INT_WALL ..
409
410 SB25         =INTERIOR-WALL  AREA = 277 NEXT-TO SPACES5-1
411                                     CONSTRUCTION = INT_WALL ..
412
413 SPACE3-1     =SPACE      SPACE-CONDITIONS = OFFICE
414                                     AREA = 1221.28925 VOLUME = 12221.4264
415                                     NUMBER-OF-PEOPLE = 7 ..
416
417 BACK-1      =EXTERIOR-WALL  HEIGHT = 10 WIDTH = 90.8
418                                     X=90.8 Y=60.5 Z=0 AZIMUTH = 0 ..
419
420 WB-1         =WINDOW      WIDTH = 6 X = 4.56 Y = 2.95 ..
421 WB-2         =WINDOW      WIDTH = 6 X = 19.72 Y = 2.95 ..
422 WB-3         =WINDOW      WIDTH = 6 X = 34.84 Y = 2.95 ..
423 WB-4         =WINDOW      WIDTH = 6 X = 50.00 Y = 2.95 ..
424 WB-5         =WINDOW      WIDTH = 6 X = 65.12 Y = 2.95 ..
425 WB-6         =WINDOW      WIDTH = 6 X = 80.28 Y = 2.95 ..
426 DB-1         =DOOR        WIDTH = 3 HEIGHT = 7
427                                     X = 28.08 Y = 0
428                                     CONSTRUCTION = DOOR2 ..
429 DB-2         =DOOR        WIDTH = 3 HEIGHT = 7
430                                     X = 41.92 Y = 0
431                                     CONSTRUCTION = DOOR2 ..
432
433 C3-1         =INTERIOR-WALL  AREA = 1221.28925 NEXT-TO ATTIC

```

```

434                                CONSTRUCTION = CEIL_MAT2 ..
435
436      F3-1      =UNDERGROUND-FLOOR  AREA = 1221.28925
437                                CONSTRUCTION = EXT_SLAB ..
438
439      SB34      =INTERIOR-WALL      AREA = 231.931 NEXT-TO SPACE4-1
440                                CONSTRUCTION = INT_WALL ..
441
442      SB35      =INTERIOR-WALL      AREA = 580 NEXT-TO SPACE5-1
443                                CONSTRUCTION = INT_WALL ..
444
445      SPACE4-1  =SPACE              SPACE-CONDITIONS = OFFICE
446                                AREA = 724.4845 VOLUME = 7249.7832
447                                NUMBER-OF-PEOPLE = 4 ..
448
449      LEFT-1    =EXTERIOR-WALL      HEIGHT = 10 WIDTH = 60.5
450                                X=0 Y=60.5 Z=0 AZIMUTH = 270 ..
451
452      WL-1      =WINDOW              WIDTH = 6 X = 4.56 Y = 2.95 ..
453      WL-2      =WINDOW              WIDTH = 6 X = 19.72 Y = 2.95 ..
454      WL-3      =WINDOW              WIDTH = 6 X = 34.84 Y = 2.95 ..
455      WL-4      =WINDOW              WIDTH = 6 X = 50.00 Y = 2.95 ..
456
457      C4-1      =INTERIOR-WALL      AREA = 724.4845 NEXT-TO ATTIC
458                                CONSTRUCTION = CEIL_MAT2 ..
459
460      F4-1      =UNDERGROUND-FLOOR  AREA = 724.4845
461                                CONSTRUCTION = EXT_SLAB ..
462
463      SB45      =INTERIOR-WALL      AREA = 277 NEXT-TO SPACE5-1
464                                CONSTRUCTION = INT_WALL ..
465
466      SPACE5-1  =SPACE              SPACE-CONDITIONS = OFFICE
467                                AREA = 1611.0899 VOLUME = 16122.1672
468                                NUMBER-OF-PEOPLE = 9 ..
469
470      C5-1      =INTERIOR-WALL      AREA = 1611.0899 NEXT-TO ATTIC
471                                CONSTRUCTION = CEIL_MAT2 ..
472
473      F5-1      =UNDERGROUND-FLOOR  AREA = 1611.0899
474                                CONSTRUCTION = EXT_SLAB ..
475
476      END ..
477      COMPUTE LOADS ..
478
479
480      $----- SYSTEM DESCRIPTION -----
481
482      INPUT SYSTEMS ..
483
484              SYSTEMS-REPORT SUMMARY=(ALL-SUMMARY)
485              REPORT-FREQUENCY = HOURLY
486              HOURLY-DATA-SAVE = FORMATTED ..
487
488
489      $ SYSTEMS SCHEDULES
490
491      FAN-1      =DAY-SCHEDULE      (1,6) (0) (7,19) (1) (20,24) (0)
492      ..
493      FAN-2      =DAY-SCHEDULE      (1,24) (0) ..
494      FAN-3      =DAY-SCHEDULE      (1,24) (1) ..
495      FAN-4      =DAY-SCHEDULE      (1,6) (0) (7,23) (1) (24) (0) ..
496      FAN-5      =DAY-SCHEDULE      (1,8) (0) (9,17) (1) (18,24) (0) ..
497
498      FAN-WEEK   =WEEK-SCHEDULE      (WD) FAN-1 (WEH) FAN-2
499      ..
500      FAN-WEEK2  =WEEK-SCHEDULE      (WD) FAN-2 (WEH) FAN-2
501      ..
502      FAN-WEEK3  =WEEK-SCHEDULE      (WD) FAN-3 (WEH) FAN-3
503      ..
504      FAN-WEEK4  =WEEK-SCHEDULE      (WD) FAN-4 (WEH) FAN-2
505      ..
506      FAN-WEEK5  =WEEK-SCHEDULE      (WD) FAN-5 (WEH) FAN-2

```

```

502 ..
503 FAN-SCHED =SCHEDULE THRU DEC 31 FAN-WEEK
504 ..
504 FAN-SCHED2 =SCHEDULE THRU DEC 31 FAN-WEEK2
505 ..
505 FAN-SCHED3 =SCHEDULE THRU DEC 31 FAN-WEEK3
506 ..
506 FAN-SCHED4 =SCHEDULE THRU DEC 31 FAN-WEEK4
507 ..
507 FAN-SCHED5 =SCHEDULE THRU DEC 31 FAN-WEEK5
508 ..
509 ..
510 $ THERMOSTAT SET-POINTS FOR HEATING AND COOLING
511 $ SET TEMPERATURES CONVERTED TO IP UNITS FROM SI UNITS
512 ..
513 HEAT-1 =DAY-SCHEDULE (1,6) (60.01) (7)
514 (69.98)
515 (8,19) (69.98) (20,24) (60.01)
516 ..
515 HEAT-2 =DAY-SCHEDULE (1,5) (60.01) (6) (64.04) (7) (68.0)
516 (8,17) (69.98) (18,24) (60.01) ..
517 HEAT-3 =DAY-SCHEDULE (1,24) (60.01) ..
518 HEAT-4 =DAY-SCHEDULE (1,24) (69.98) ..
519 ..
520 HEAT-WEEK =WEEK-SCHEDULE (MON,FRI) HEAT-1 (SAT) HEAT-3 (SUN) HEAT-3
521 (HOL) HEAT-3 ..
522 HEAT-WEEK2 =WEEK-SCHEDULE (MON,FRI) HEAT-3 (SAT) HEAT-3 (SUN)
523 HEAT-3
524 (HOL) HEAT-3 ..
524 HEAT-WEEK3 =WEEK-SCHEDULE (MON,FRI) HEAT-4 (SAT) HEAT-4 (SUN)
525 HEAT-4
526 (HOL) HEAT-4 ..
527 ..
528 HEAT-SCHED =SCHEDULE THRU DEC 31 HEAT-WEEK
529 ..
529 HEAT-SCHED2 =SCHEDULE THRU DEC 31 HEAT-WEEK2
530 ..
530 HEAT-SCHED3 =SCHEDULE THRU DEC 31 HEAT-WEEK3
531 ..
532 ..
533 COOLOFF =SCHEDULE THRU DEC 31 (ALL) (1,24) (1)
534 ..
534 HEATOFF =SCHEDULE THRU DEC 31 (ALL) (1,24) (1)
535 ..
536 ..
537 COOL-1 =DAY-SCHEDULE (1,6) (84.99) (7)
538 (75.00)
539 (8,18) (75.00) (19,24) (84.99)
540 ..
539 COOL-2 =DAY-SCHEDULE (1,5) (84.99) (6) (78.08) (7) (77.0)
540 (8,17) (75.00) (18,24) (84.99) ..
541 COOL-3 =DAY-SCHEDULE (1,24) (84.99) ..
542 COOL-4 =DAY-SCHEDULE (1,24) (75.00) ..
543 ..
544 COOL-WEEK =WEEK-SCHEDULE (MON,FRI) COOL-1 (SAT) COOL-3 (SUN) COOL-3
545 (HOL) COOL-3 ..
546 COOL-WEEK2 =WEEK-SCHEDULE (MON,FRI) COOL-3 (SAT) COOL-3 (SUN)
547 COOL-3
548 (HOL) COOL-3 ..
548 COOL-WEEK3 =WEEK-SCHEDULE (MON,FRI) COOL-4 (SAT) COOL-4 (SUN)
549 COOL-4
550 (HOL) COOL-4 ..
551 ..
552 COOL-SCHED =SCHEDULE THRU DEC 31 COOL-WEEK
553 ..
553 COOL-SCHED2 =SCHEDULE THRU DEC 31 COOL-WEEK2
554 ..

```

```

554 COOL-SCHED3 =SCHEDULE      THRU DEC 31  COOL-WEEK3
..
555
556
557 HVAC-HEAT   =SCHEDULE      THRU DEC 31  (ALL) (1,24) (1)
..
558 HVAC-COOL   =SCHEDULE      THRU DEC 31  (ALL) (1,24) (1)
..
559
560 24HR-OFF    =SCHEDULE      THRU DEC 31  (ALL) (1,24) (0)
..
561
562 DHW-SCHED    =SCHEDULE      THRU DEC 31  (ALL) (1,24) (1)
..
563 DHWINLETSCH-1 =SCHEDULE      THRU DEC 31  (ALL) (1,24) (140)
..
564
565 INT-1        =DAY-SCHEDULE  (1,7) (0) (8) (0.35) (9) (0.69) (10)
(0.43)
566 (11) (0.37) (12) (0.43) (13) (0.58) (14) (0.48)
567 (15,16) (0.37) (17) (0.46) (18) (0.62)
568 (19) (0.12) (20,21) (0.04) (22,24) (0)
..
569 INT-2        =DAY-SCHEDULE  (1,7) (0) (8) (0.16) (9) (0.14) (10) (0.21)
570 (11) (0.18) (12) (0.25) (13) (0.21) (14) (0.13)
571 (15) (0.08) (16) (0.04) (17) (0.05)
572 (18) (0.06) (19,24) (0) ..
573 INT-3        =DAY-SCHEDULE  (1,24) (0) ..
574 INT-WEEK     =WEEK-SCHEDULE (MON,FRI) INT-3 (SAT) INT-3 (SUN) INT-3
575 (HOL) INT-3 ..
576 INT-SHED     = SCHEDULE      THRU DEC 31  INT-WEEK
..
577
578
579 $ SYSTEM DESCRIPTION
580
581 ZAIR         =ZONE-AIR      OA-CFM/PER=
17
582
583 EXHAUST-CFM =
0
584 EXHAUST-EFF =
0.75
585
586 EXHAUST-STATIC = 0
..
587
588 CONTROL     = ZONE-CONTROL  DESIGN-HEAT-T =
70
589
590 DESIGN-COOL-T =
75
591 HEAT-TEMP-SCH = HEAT-SCHED
592 COOL-TEMP-SCH = COOL-SCHED
593 THERMOSTAT-TYPE =
PROPORTIONAL
594 THROTTLING-RANGE = 0.1
..
595
596 SPACE1-1    =ZONE          ZONE-AIR=ZAIR
597
598 SIZING-OPTION=ADJUST-LOADS
599
600 ZONE-CONTROL=CONTROL ..
601
602 SPACE2-1    =ZONE          LIKE SPACE1-1 ..
603 SPACE3-1    =ZONE          LIKE SPACE1-1 ..
604 SPACE4-1    =ZONE          LIKE SPACE1-1 ..
605 SPACE5-1    =ZONE          LIKE SPACE1-1 ..
606
607 ATTIC       =ZONE          ZONE-TYPE=UNCONDITIONED
..
608
609

```



```

606
607
608 S-AIR      =SYSTEM-AIR      MAX-OA-FRACTION =
609 1.0
610
611
612 S-CONT     =SYSTEM-CONTROL  COOLING-SCHEDULE=
613 COOLOFF
614
615
616
617
618 S-FAN      =SYSTEM-FANS     FAN-SCHEDULE=FAN-SCHED
619
620
621
622
623
624
625
626
627
628
629
630 $ PNNL COOLING COIL CURVE-FIT
631 HPACCoolCapFT =
632 CURVE-FIT
633
634
635
636
637
638
639
640
641
642
643
644
645
646
647 S-EQUIP    =SYSTEM-EQUIPMENT  COOL-CAP-FT =
648 SDL-C3
649
650
651
652
653
654
655
656
657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743
744
745
746
747
748
749
750
751
752
753
754
755
756
757
758
759
760
761
762
763
764
765
766
767
768
769
770
771
772
773
774
775
776
777
778
779
780
781
782
783
784
785
786
787
788
789
790
791
792
793
794
795
796
797
798
799
800
801
802
803
804
805
806
807
808
809
810
811
812
813
814
815
816
817
818
819
820
821
822
823
824
825
826
827
828
829
830
831
832
833
834
835
836
837
838
839
840
841
842
843
844
845
846
847
848
849
850
851
852
853
854
855
856
857
858
859
860
861
862
863
864
865
866
867
868
869
870
871
872
873
874
875
876
877
878
879
880
881
882
883
884
885
886
887
888
889
890
891
892
893
894
895
896
897
898
899
900
901
902
903
904
905
906
907
908
909
910
911
912
913
914
915
916
917
918
919
920
921
922
923
924
925
926
927
928
929
930
931
932
933
934
935
936
937
938
939
940
941
942
943
944
945
946
947
948
949
950
951
952
953
954
955
956
957
958
959
960
961
962
963
964
965
966
967
968
969
970
971
972
973
974
975
976
977
978
979
980
981
982
983
984
985
986
987
988
989
990
991
992
993
994
995
996
997
998
999

```

```

650          SDL-C13
          COOL-EIR-FFLR =
651          SDL-C18
          COOL-SH-FT
          =SDL-C23

652          COIL-BF-FT =
          HPACCoolCapFT

653          COIL-BF-FCFM =
          HPACCoolCapFFF
654          COIL-BF-FFLR =
          HPACCOOLPLFFPLR

655          COIL-BF=0.19

656          COOL-FT-MIN=
          70
657          HEAT-CAP-FT =
          SDL-C55
658          HEATING-EIR =
          0.29751543
659          HEAT-EIR-FT =
          SDL-C60
660          HEAT-EIR-FFLR =
          SDL-C65
661          DEFROST-FRAC-FT =
          HPACCOOLEIRFT
662          OUTSIDE-FAN-T =
          45
663          OUTSIDE-FAN-MODE =
          INTERMITTENT
664          COMPRESSOR-TYPE =
          SINGLE-SPEED
665          RATED-CCAP-FCFM =
          SDL-C78
666          RATED-SH-FCFM=
          SDL-C85
667          RATED-CEIR-FCFM=
          SDL-C93
668          RATED-HCAP-FCFM=
          SDL-C100
669          CRANKCASE-HEAT=
          0.05
670          CRANKCASE-MAX-T= 39.92
          ..

671
672
673  S-TERM      =SYSTEM-TERMINAL REHEAT-DELTA-T=
          50

674          MIN-CFM-RATIO= 1.0
          ..

675
676  SYST-1      =SYSTEM          SYSTEM-TYPE=
          PSZ

677          SYSTEM-CONTROL= S-CONT
678          SYSTEM-FANS= S-FAN
679          SYSTEM-TERMINAL= S-TERM
680          SYSTEM-EQUIPMENT=
          S-EQUIP
681          HEAT-SOURCE=
          HEAT-PUMP

682          PREHEAT-SOURCE=
          HEAT-PUMP
683          ECONO-LIMIT-T=
          82.4
684          ECONO-LOW-LIMIT=
          32
685          RETURN-AIR-PATH= DIRECT
686          SIZING-OPTION =
          NON-COINCIDENT

```

```

687
ZONE-NAMES=(SPACE5-1,SPACE1-1,SPACE2-1
688
SPACE3-1,SPACE4-1,ATTIC)
..
689
690
691 HP-1 = PLANT-ASSIGNMENT SYSTEM-NAMES = (SYST-1)
692 HP-LOOP-HEATING = FROM-SYSTEMS
693 HP-LOOP-COOLING = FROM-SYSTEMS
694 DHW-SIZE = 40
695 DHW-GAL/MIN =
0.0486
696 DHW-SCH = DHW-SCHED
697 DHW-INLET-T-SCH = DHWINLETSCH-1
698 DHW-SUPPLY-T =
131
699 DHW-TYPE = ELECTRIC
700 DHW-EIR = 1
701 DHW-EIR-FT = DHWHPEIRFT
702 DHW-HEAT-RATE-FT = DHWHPCAPFT
703 DHW-EIR-FPLR = DHWGEIRFPLR
704 DHW-PUMP-ELEC = 0
705 MAX-FLUID-T = 140
706 MIN-FLUID-T = 50
707 FLUID-VOLUME = 15
..
708
709
710 $===== HOURLY-REPORT FOR SYSTEM
=====
711
712 $ HOURLY-REPORT FOR SYSTEM PART
713 HRSCH-2 = SCHEDULE
714 THRU DEC 31 (ALL) (1,24) (1) ..
715
716 S1_ZT = REPORT-BLOCK
717 VARIABLE-TYPE=SPACE1-1
718 VARIABLE-LIST=(6,14)
..
719
720 S2_ZT = REPORT-BLOCK
721 VARIABLE-TYPE=SPACE2-1
722 VARIABLE-LIST=(6,14)
..
723
724 S3_ZT = REPORT-BLOCK
725 VARIABLE-TYPE=SPACE3-1
726 VARIABLE-LIST=(6,14) ..
727
728 S4_ZT = REPORT-BLOCK
729 VARIABLE-TYPE=SPACE4-1
730 VARIABLE-LIST=(6,14)
..
731
732 S5_ZT = REPORT-BLOCK
733 VARIABLE-TYPE=SPACE5-1
734 VARIABLE-LIST=(6,14)
..
735
736 SYS1 = REPORT-BLOCK
737 VARIABLE-TYPE=SYST-1
738 VARIABLE-LIST=(1,2) ..
739
740 PPRT1 = HOURLY-REPORT
741 REPORT-SCHEDULE = HRSCH-2
742 REPORT-BLOCK = (S1_ZT,S2_ZT,S3_ZT,S4_ZT,S5_ZT,SYST1) ..
743
744 $=====
745

```

```
746
747 END ..
748 COMPUTE SYSTEMS ..
749
750
751 INPUT PLANT ..
752
753         PLANT-REPORT SUMMARY=(ALL-SUMMARY)
754         REPORT-FREQUENCY = HOURLY
755         HOURLY-DATA-SAVE = FORMATTED ..
756
757 $===== HOURLY-REPORT FOR PLANT
758 =====
759 HRSCH-3      = SCHEDULE
760              THRU DEC 31 (ALL) (1,24) (1) ..
761
762 PLT          = REPORT-BLOCK
763              VARIABLE-TYPE=PLANT
764              VARIABLE-LIST=(3) ..
765
766 ENDU        = REPORT-BLOCK
767              VARIABLE-TYPE=END-USE
768              VARIABLE-LIST=(1,3,5,6,9)
769              ..
770
771 PFRT1       = HOURLY-REPORT
772              REPORT-SCHEDULE = HRSCH-3
773              REPORT-BLOCK = (PLT,ENDU) ..
774
775 $=====
776
777 END ..
778 COMPUTE PLANT ..
779
780 STOP ..
```

2.2.2 Reference Model 2: Five-Zone Model in Houston, TX (PVAV System)

In this section the DOE-2 input file for "Case 2: Five-Zone Model in Houston, TX" is described.

```

1  $===== SIMULATION ZONING =====
2
3  INPUT LOADS ..
4
5  TITLE          LINE-1 *SAMPLE PROVIDED BY PROF.JEFF HABERL*
6                LINE-2 *HOUSTON, TX, CLIMATE ZONE 2A*
7                LINE-3 *ASHRAE 90.1-2016 REQUIREMENTS SATISFIED*
8                LINE-4 *STUDY FOR BUILDING OCCUPANCY PROFILE ANALYSIS* ..
9
10             RUN-PERIOD          JAN 1 2019 THRU DEC 31 2019  ..
11
12             ABORT                ERRORS ..
13             DIAGNOSTIC           WARNINGS ..
14             LOADS-REPORT         SUMMARY = (ALL-SUMMARY)
15                                 REPORT-FREQUENCY = HOURLY
16                                 HOURLY-DATA-SAVE = FORMATTED
17                                 VERIFICATION = (ALL-VERIFICATION) ..
18
19             BUILDING-LOCATION      LATITUDE=30.0
20                                 LONGITUDE=95.37
21                                 GROUND-T = (69.314, 69.224, 69.368, 69.512,
22                                 69.692, 73.634, 74.3, 74.444, 74.48, 70.448,
23                                 69.818, 69.458)
24                                 DAYLIGHT-SAVINGS = NO
25                                 ALTITUDE=95.14
26                                 TIME-ZONE=6
27                                 AZIMUTH=0.0  ..
28
29
30  $ BUILDING DESCRIPTION
31
32  $===== BUILDING CONSTRUCTION =====
33
34  $ CONSTRUCTION AND GLASS-TYPES
35
36  $ MATERIAL PROPERTY (IP UNITS)
37  $ ALL VALUES CONVERTED FROM SI UNITS IN PNNL SMALL OFFICE MODEL FOR 90.1-2016
38  $ ROOF AND CEILING PROPERTY
39  ROOF_BUIL      = MAT                THICKNESS = 0.03116798
40                                           CONDUCTIVITY = 0.092446272
41                                           DENSITY = 69.9193264
42                                           SPECIFIC-HEAT = 0.348715014  ..
43
44
45  ROOF_INS_1     = MAT                RESISTANCE = 24.52377767  ..
46
47  ROOF_INS_2     = MAT                RESISTANCE = 35.40275850  ..
48
49  ROOF_SUR_1     = MAT                THICKNESS = 0.002624672
50                                           CONDUCTIVITY = 26.16229498
51                                           DENSITY = 488.4364373
52                                           SPECIFIC-HEAT = 0.11942295  ..
53
54  CEIL_MAT       = MAT                THICKNESS = 0.041666668
55                                           CONDUCTIVITY = 0.032933984
56                                           DENSITY = 17.97925536
57                                           SPECIFIC-HEAT = 0.31981466  ..
58
59  ROOF_ASPHT     = MAT                THICKNESS = 0.010498688
60                                           CONDUCTIVITY = 0.023111568
61                                           DENSITY = 69.9193264
62                                           SPECIFIC-HEAT = 0.300945834  ..
63
64  ROOF_WOOD      = MAT                THICKNESS = 0.052165356
65                                           CONDUCTIVITY = 0.069334704
66                                           DENSITY = 33.96081568
67                                           SPECIFIC-HEAT = 0.289003539  ..
68
69
70  $ SLAB PROPERTY
71  SLAB_CONC200   = MAT                THICKNESS = 0.666666688
72                                           CONDUCTIVITY = 1.334693052
73                                           DENSITY = 144.9577463

```

```

74                                     SPECIFIC-HEAT = 0.198719789 ..
75
76 SLAB_CONC100 = MAT                 THICKNESS = 0.333333344
77                                     CONDUCTIVITY = 1.334693052
78                                     DENSITY = 144.9577463
79                                     SPECIFIC-HEAT = 0.198719789 ..
80
81 SLAB_CARP = MAT                     RESISTANCE = 1.22923033 ..
82
83
84 $ WALL PROPERTY
85 WALL_STU = MAT                     THICKNESS = 0.083333336
86                                     CONDUCTIVITY = 0.416008224
87                                     DENSITY = 115.8663123
88                                     SPECIFIC-HEAT = 0.200630556 ..
89
90 WALL_GYP1 = MAT                    THICKNESS = 0.052165356
91                                     CONDUCTIVITY = 0.092446272
92                                     DENSITY = 49.942376
93                                     SPECIFIC-HEAT = 0.260342031 ..
94
95 WALL_GYP2 = MAT                    THICKNESS = 0.041666668
96                                     CONDUCTIVITY = 0.092446272
97                                     DENSITY = 49.942376
98                                     SPECIFIC-HEAT = 0.260342031 ..
99
100 WALL_INS_1 = MAT                   RESISTANCE = 9.72589032 ..
101
102 WALL_INS_2 = MAT                   RESISTANCE = 9.05708346 ..
103
104
105 $ WINDOW PROPERTY
106 WIN_GLS3 = GLASS-TYPE              GLASS-CONDUCTANCE = 0.6535
107                                     VIS-TRANS = 0.312
108                                     SHADING-COEF =
109                                     0.286206897
110                                     PANES = 2 ..
111
112 DOOR1 = GLASS-TYPE                 GLASS-CONDUCTANCE = 0.370
113                                     SHADING-COEF = 0.7 ..
114
115 AIR-LAYER = CONSTRUCTION           U = 1.11 ..
116
117
118 $ MATERIAL LAYERS
119 ATTIC-R1 =LAYERS =MAT=(AR02,PW04)
120 ..
121
122 ATTIC-R2 =LAYERS =MAT=(PW04) ..
123
124 ROOF_1 =LAYERS =MAT=(ROOF_INS_2,GP02) ..
125
126 EX_SLAB_1 =LAYERS =MAT=(SLAB_CONC200,CP02) ..
127
128 EX_WALL_1 =LAYERS =MAT=(SC01,GP02,WALL_INS_2,GP02) ..
129
130 IN_WALL_1 =LAYERS =MAT=(GP01,GP01) ..
131
132 IN_SLAB_1 =LAYERS =MAT=(SLAB_CONC100,CP02) ..
133
134 CEIL_MAT1 =LAYERS =MAT=(AC02,GP01) ..
135
136
137 $ MATERIAL CONSTRUCTION
138 EXT_SLAB =CONSTRUCTION              LAYERS = EX_SLAB_1
139                                     ABSORPTANCE = 0.7 ..
140
141 NONRES_EXT_WALL =CONSTRUCTION      LAYERS = EX_WALL_1
142                                     ABSORPTANCE = 0.7 ..
143
144 INT_WALL =CONSTRUCTION              LAYERS = IN_WALL_1
145                                     ABSORPTANCE = 0.7 ..
146
147 CEIL_MAT2 =CONSTRUCTION             LAYERS = ROOF_1
148                                     ABSORPTANCE = 0.7 ..
149
150 ATTIC-ROOF =CONSTRUCTION            LAYERS = ATTIC-R1
151                                     ABSORPTANCE = 0.7 ..
152
153 ATTIC-SOFFIT =CONSTRUCTION          LAYERS = ATTIC-R2
154                                     ABSORPTANCE = 0.7 ..
155
156 DOOR2 =CONSTRUCTION                U = 1.2139351092
157                                     ABSORPTANCE = 0.7 ..

```

```

144
145 $ OCCUPANCY SCHEDULE
146 OC-1      =DAY-SCHEDULE      (1,6) (0.0)
147          (7) (0.11)
148          (8) (0.21)
149          (9,12) (1.0)
150          (13) (0.53)
151          (14,17) (1.0)
152          (18) (0.32)
153          (19,22) (0.11)
154          (23) (0.05)
155          (24) (0.0) ..
156
157 OC-2      =DAY-SCHEDULE      (1,6) (0.0)
158          (7,8) (0.1)
159          (9,12) (0.3)
160          (13,17) (0.1)
161          (18,19) (0.05)
162          (20,24) (0.0) ..
163
164 OC-3      =DAY-SCHEDULE      (1,6) (0.0)
165          (7,18) (0.05)
166          (19,24) (0.0) ..
167
168 OC-4      =DAY-SCHEDULE      (1,24) (0.0) ..
169 OC-5      =DAY-SCHEDULE      (1,24) (1.0) ..
170
171 OC-WEEK   =WEEK-SCHEDULE      (WD) OC-1 (SAT) OC-4 (SUN) OC-4 (HOL) OC-4 ..
172 OC-WEEK2  =WEEK-SCHEDULE      (WD) OC-4 (SAT) OC-4 (SUN) OC-4 (HOL) OC-4 ..
173 OC-WEEK3  =WEEK-SCHEDULE      (WD) OC-5 (SAT) OC-5 (SUN) OC-5 (HOL) OC-5 ..
174
175 OCCUPY-1  =SCHEDULE                THRU DEC 31 OC-WEEK ..
176 OCCUPY-2  =SCHEDULE                THRU DEC 31 OC-WEEK2 ..
177 OCCUPY-3  =SCHEDULE                THRU DEC 31 OC-WEEK3 ..
178
179
180 $ LIGHTING SCHEDULE
181
182 LT-1      =DAY-SCHEDULE      (1,5) (0.18)
183          (6,7) (0.23)
184          (8) (0.42)
185          (9,12) (0.9)
186          (13) (0.8)
187          (14,17) (0.9)
188          (18) (0.61)
189          (19,20) (0.42)
190          (21,22) (0.32)
191          (23) (0.23)
192          (24) (0.18) ..
193
194 LT-0      =DAY-SCHEDULE      (1,6) (0.0)
195          (7) (0.11)
196          (8) (0.21)
197          (9,12) (1.0)
198          (13) (0.53)
199          (14,17) (1.0)
200          (18) (0.32)
201          (19,22) (0.11)
202          (23) (0.05)
203          (24) (0.0) ..
204
205 LT-2      =DAY-SCHEDULE      (1,6) (0.05)
206          (7,8) (0.1)
207          (9,12) (0.3)
208          (13,17) (0.15)
209          (18,24) (0.05) ..
210
211 LT-3      =DAY-SCHEDULE      (1,24) (0.18) ..
212 LT-4      =DAY-SCHEDULE      (1,24) (0.0) ..
213 LT-5      =DAY-SCHEDULE      (1,24) (1.0) ..
214
215
216 LT-WEEK   =WEEK-SCHEDULE      (WD) LT-1 (SAT) LT-3 (SUN) LT-3 (HOL) LT-3 ..

```

```

217 LT-WEEK2      =WEEK-SCHEDULE      (WD) LT-3 (SAT) LT-3 (SUN) LT-3 (HOL) LT-3 ..
218 LT-WEEK3      =WEEK-SCHEDULE      (WD) LT-5 (SAT) LT-5 (SUN) LT-5 (HOL) LT-5 ..
219
220
221 LIGHTS-1       =SCHEDULE              THRU DEC 31 LT-WEEK ..
222 LIGHTS-2       =SCHEDULE              THRU DEC 31 LT-WEEK2 ..
223 LIGHTS-3       =SCHEDULE              THRU DEC 31 LT-WEEK3
..
224
225
226 $ OFFICE EQUIPMENT SCHEDULE
227 EQ-1           =DAY-SCHEDULE      (1,5) (0.5)
228                (6,12) (1.0)
229                (13) (0.94)
230                (14,17) (1.0)
231                (18) (0.5)
232                (19,24) (0.2) ..
233
234 EQ-0           =DAY-SCHEDULE      (1,6) (0.0)
235                (7) (0.11)
236                (8) (0.21)
237                (9,12) (1.0)
238                (13) (0.53)
239                (14,17) (1.0)
240                (18) (0.32)
241                (19,22) (0.11)
242                (23) (0.05)
243                (24) (0.0) ..
244
245 EQ-2           =DAY-SCHEDULE      (1,6) (0.3)
246                (7,8) (0.4)
247                (9,12) (0.5)
248                (13,17) (0.35)
249                (18,24) (0.3) ..
250
251 EQ-3           =DAY-SCHEDULE      (1,24) (0.2) ..
252 EQ-4           =DAY-SCHEDULE      (1,24) (0.0) ..
253 EQ-5           =DAY-SCHEDULE      (1,24) (1.0) ..
254
255
256 EQ-WEEK        =WEEK-SCHEDULE      (WD) EQ-1 (SAT) EQ-3 (SUN) EQ-3 (HOL) EQ-3 ..
257 EQ-WEEK2       =WEEK-SCHEDULE      (WD) EQ-3 (SAT) EQ-3 (SUN) EQ-3 (HOL) EQ-3 ..
258 EQ-WEEK3       =WEEK-SCHEDULE      (WD) EQ-5 (SAT) EQ-5 (SUN) EQ-5 (HOL) EQ-5 ..
259
260
261 EQUIP-1        =SCHEDULE              THRU DEC 31 EQ-WEEK ..
262 EQUIP-2        =SCHEDULE              THRU DEC 31 EQ-WEEK2 ..
263 EQUIP-3        =SCHEDULE              THRU DEC 31 EQ-WEEK3 ..
264
265
266 $ INFILTRATION SCHEDULE
267 IF-1           =DAY-SCHEDULE      (1,6) (1.0)
268                (7,19) (0.25)
269                (20,24) (1.0) ..
270
271 IF-2           =DAY-SCHEDULE      (1,7) (1.0)
272                (8,18) (0.25)
273                (19,24) (1.0) ..
274
275 IF-3           =DAY-SCHEDULE      (1,24) (0.0) ..
276 IF-4           =DAY-SCHEDULE      (1,24) (1.0) ..
277 IF-5           =DAY-SCHEDULE      (1,24) (0.25) ..
278
279 IF-6           =DAY-SCHEDULE      (1,6) (1.0)
280                (7,23) (0.25)
281                (24) (1.0) ..
282
283 IF-WEEK        =WEEK-SCHEDULE      (WD) IF-1 (SAT) IF-2 (SUN) IF-4 (HOL) IF-4 ..
284 IF-WEEK2       =WEEK-SCHEDULE      (WD) IF-4 (SAT) IF-4 (SUN) IF-4 (HOL) IF-4 ..
285 IF-WEEK3       =WEEK-SCHEDULE      (WD) IF-5 (SAT) IF-5 (SUN) IF-5 (HOL) IF-5 ..
286
287 INFIL-SCH      =SCHEDULE              THRU DEC 31 IF-WEEK ..
288 INFIL-SCH2     =SCHEDULE              THRU DEC 31 IF-WEEK2 ..

```



```

289 INFIL-SCH3   =SCHEDULE           THRU DEC 31 IF-WEEK3 ..
290
291
292
293 $----- SPACE DEFAULTS & DESCRIPTION -----
294
295
296 $ SET DEFAULT VALUE
297
298           SET-DEFAULT FOR SPACE FLOOR-WEIGHT = 0 ..
299           SET-DEFAULT FOR WINDOW HEIGHT=5.0
300                               GLASS-TYPE=WIN_GLS3 Y=1 ..
301           SET-DEFAULT FOR EXTERIOR-WALL CONSTRUCTION=NONRES_EXT_WALL ..
302
303
304 $ GENERAL SPACE DEFINITION
305
306 OFFICE       =SPACE-CONDITIONS  PEOPLE-SCHEDULE      =OCCUPY-1
307                               NUMBER-OF-PEOPLE      =31
308                               PEOPLE-HEAT-GAIN       =450
309                               LIGHTING-SCHEDULE      =LIGHTS-1
310                               LIGHTING-W/SQFT        = 0.79
311                               EQUIP-SCHEDULE         = EQUIP-1
312                               EQUIPMENT-W/SQFT       = 0.63
313                               INF-METHOD           = AIR-CHANGE
314                               AIR-CHANGES/HR       = 0.0
315                               INF-SCHEDULE          =INFIL-SCH2 ..
316
317
318           $ SPECIFIC SPACE DETAILS
319
320 $ ATTIC
321 ATTIC-SC     = SPACE-CONDITIONS
322             ZONE-TYPE = UNCONDITIONED
323             FLOOR-WEIGHT = 0 ..
324
325 ATTIC       = SPACE   S-C = ATTIC-SC  AREA = 6113.686  VOLUME = 24533.31
326             X = 0   Y = 0   Z = 0   AZ = 0 ..
327 N-ROOF = POLYGON
328         (92.81,62.53) (-1.97,62.53) (30.28,32.03) (60.56,32.03) ..
329 S-ROOF = POLYGON
330         (-1.97,-1.97) (92.81,-1.97) (60.56,32.03) (30.28,32.03) ..
331 E-GABLE = POLYGON
332         (0,0) (64.5,0) (32.25,34) ..
333 W-GABLE = POLYGON
334         (-1.97,62.53,10) (-1.97,-1.97,10) (30.28,30.28,20.77) ..
335
336
337
338 $ ROOF RAISED
339 N-ROOF-EXT = ROOF           CONSTRUCTION = ATTIC-ROOF
340                               POLYGON = S-ROOF
341                               TILT =18.5, AZ = 0,
342                               X= 90.84 Y = 60.56 Z = 10.0 ..
343
344 S-ROOF-EXT = ROOF           CONSTRUCTION = ATTIC-ROOF
345                               POLYGON = S-ROOF
346                               TILT =18.5, AZ = 180, Z = 10.0 ..
347
348 E-GABLE-EXT = ROOF          CONSTRUCTION = ATTIC-ROOF
349                               POLYGON = E-GABLE
350                               TILT =18.2, AZ = 90
351                               X = 92.81 Y = -1.97 Z = 10.0 ..
352
353 W-GABLE-EXT = ROOF          CONSTRUCTION = ATTIC-ROOF
354                               POLYGON = E-GABLE
355                               TILT =18.2, AZ = 270
356                               X = -1.97 Y = 62.53 Z = 10.0 ..
357
358
359 N-ROOF-SOFFIT = BUILDING-SHADE HEIGHT = 1.97  WIDTH = 94.78
360                               X=-1.97 Y=60.6 Z=10
361                               TRANSMITTANCE = 0.0

```

```

362                                AZIMUTH = 180 TILT = 180 ..
363 S-ROOF-SOFFIT = BUILDING-SHADE HEIGHT = 1.97 WIDTH =
94.78
364                                X=-1.97 Y=0 Z=10
365                                TRANSMITTANCE = 0.0
366                                AZIMUTH = 180 TILT = 180 ..
367 E-ROOF-SOFFIT = BUILDING-SHADE HEIGHT = 1.97 WIDTH =
60.56
368                                X=90.85 Y=0 Z=10
369                                TRANSMITTANCE = 0.0
370                                AZIMUTH = 90 TILT = 180 ..
371 W-ROOF-SOFFIT = BUILDING-SHADE HEIGHT = 1.97 WIDTH =
60.56
372                                X=0 Y=0 Z=10
373                                TRANSMITTANCE = 0.0
374                                AZIMUTH = 90 TILT = 180 ..
375
376
377
378 SPACE1-1      =SPACE              SPACE-CONDITIONS = OFFICE
379                                AREA = 1221.28925 VOLUME = 12221.4264
380                                NUMBER-OF-PEOPLE = 7 ..
381 FRONT-1      =EXTERIOR-WALL      HEIGHT = 10 WIDTH = 90.8
382                                X=0 Y=0 Z=0 AZIMUTH = 180 ..
383
384 WF-1          =WINDOW              WIDTH = 6 X = 4.56 Y = 2.95 ..
385 WF-2          =WINDOW              WIDTH = 6 X = 19.72 Y = 2.95 ..
386 WF-3          =WINDOW              WIDTH = 6 X = 34.84 Y = 2.95 ..
387 WF-4          =WINDOW              WIDTH = 6 X = 50.00 Y = 2.95 ..
388 WF-5          =WINDOW              WIDTH = 6 X = 65.12 Y = 2.95 ..
389 WF-6          =WINDOW              WIDTH = 6 X = 80.28 Y = 2.95 ..
390 DF-1          =WINDOW              WIDTH = 6 HEIGHT = 7
391                                X = 42.42 Y = 0
392                                GLASS-TYPE=WIN_GLS3 ..
393
394 C1-1          =INTERIOR-WALL      AREA = 1221.28925 NEXT-TO ATTIC
395                                CONSTRUCTION = CEIL_MAT2 ..
396
397 F1-1          =UNDERGROUND-FLOOR  AREA = 1221.28925 CONSTRUCTION = EXT_SLAB ..
398
399 SB12          =INTERIOR-WALL      AREA=231.931 NEXT-TO SPACE2-1
400                                CONSTRUCTION = INT_WALL ..
401
402 SB14          =INTERIOR-WALL      LIKE SB12 NEXT-TO SPACE4-1 ..
403 SB15          =INTERIOR-WALL      AREA 580 NEXT-TO SPACE5-1
404                                CONSTRUCTION = INT_WALL ..
405
406 SPACE2-1      =SPACE              SPACE-CONDITIONS = OFFICE
407                                AREA = 724.4845 VOLUME = 7249.7832
408                                NUMBER-OF-PEOPLE = 4 ..
409
410 RIGHT-1       =EXTERIOR-WALL      HEIGHT = 10 WIDTH = 60.5
411                                X=90.8 Y=0 Z=0 AZIMUTH = 90 ..
412
413 WR-1          =WINDOW              WIDTH = 6 X = 4.56 Y = 2.95 ..
414 WR-2          =WINDOW              WIDTH = 6 X = 19.72 Y = 2.95 ..
415 WR-3          =WINDOW              WIDTH = 6 X = 34.84 Y = 2.95 ..
416 WR-4          =WINDOW              WIDTH = 6 X = 50.00 Y = 2.95 ..
417
418 C2-1          =INTERIOR-WALL      AREA = 724.4845 NEXT-TO ATTIC
419                                CONSTRUCTION = CEIL_MAT2 ..
420
421 F2-1          =UNDERGROUND-FLOOR  AREA = 724.4845 CONSTRUCTION = EXT_SLAB ..
422
423 SB23          =INTERIOR-WALL      AREA = 231.931 NEXT-TO SPACE3-1
424                                CONSTRUCTION = INT_WALL ..
425
426 SB25          =INTERIOR-WALL      AREA = 277 NEXT-TO SPACE5-1
427                                CONSTRUCTION = INT_WALL ..
428
429 SPACE3-1      =SPACE              SPACE-CONDITIONS = OFFICE
430                                AREA = 1221.28925 VOLUME = 12221.4264
431                                NUMBER-OF-PEOPLE = 7 ..

```

```

432
433     BACK-1     =EXTERIOR-WALL     HEIGHT = 10  WIDTH = 90.8
434                                     X=90.8  Y=60.5  Z=0  AZIMUTH = 0  ..
435
436     WB-1     =WINDOW             WIDTH = 6  X = 4.56  Y = 2.95  ..
437     WB-2     =WINDOW             WIDTH = 6  X = 19.72  Y = 2.95  ..
438     WB-3     =WINDOW             WIDTH = 6  X = 34.84  Y = 2.95  ..
439     WB-4     =WINDOW             WIDTH = 6  X = 50.00  Y = 2.95  ..
440     WB-5     =WINDOW             WIDTH = 6  X = 65.12  Y = 2.95  ..
441     WB-6     =WINDOW             WIDTH = 6  X = 80.28  Y = 2.95  ..
442     DB-1     =DOOR              WIDTH = 3  HEIGHT = 7
443                                     X = 28.08  Y = 0
444                                     CONSTRUCTION = DOOR2  ..
445     DB-2     =DOOR              WIDTH = 3  HEIGHT = 7
446                                     X = 41.92  Y = 0
447                                     CONSTRUCTION = DOOR2  ..
448
449     C3-1     =INTERIOR-WALL     AREA = 1221.28925  NEXT-TO ATTIC
450                                     CONSTRUCTION = CEIL_MAT2  ..
451
452     F3-1     =UNDERGROUND-FLOOR  AREA = 1221.28925
453                                     CONSTRUCTION = EXT_SLAB  ..
454
455     SB34     =INTERIOR-WALL     AREA = 231.931  NEXT-TO SPACE4-1
456                                     CONSTRUCTION = INT_WALL  ..
457
458     SB35     =INTERIOR-WALL     AREA = 580  NEXT-TO SPACE5-1
459                                     CONSTRUCTION = INT_WALL  ..
460
461     SPACE4-1 =SPACE             SPACE-CONDITIONS = OFFICE
462                                     AREA = 724.4845  VOLUME = 7249.7832
463                                     NUMBER-OF-PEOPLE = 4  ..
464
465     LEFT-1   =EXTERIOR-WALL     HEIGHT = 10  WIDTH = 60.5
466                                     X=0  Y=60.5  Z=0  AZIMUTH = 270  ..
467
468     WL-1     =WINDOW             WIDTH = 6  X = 4.56  Y = 2.95  ..
469     WL-2     =WINDOW             WIDTH = 6  X = 19.72  Y = 2.95  ..
470     WL-3     =WINDOW             WIDTH = 6  X = 34.84  Y = 2.95  ..
471     WL-4     =WINDOW             WIDTH = 6  X = 50.00  Y = 2.95  ..
472
473     C4-1     =INTERIOR-WALL     AREA = 724.4845  NEXT-TO ATTIC
474                                     CONSTRUCTION = CEIL_MAT2  ..
475
476     F4-1     =UNDERGROUND-FLOOR  AREA = 724.4845
477                                     CONSTRUCTION = EXT_SLAB  ..
478
479     SB45     =INTERIOR-WALL     AREA = 277  NEXT-TO SPACE5-1
480                                     CONSTRUCTION = INT_WALL  ..
481
482     SPACE5-1 =SPACE             SPACE-CONDITIONS = OFFICE
483                                     AREA = 1611.0899  VOLUME = 16122.1672
484                                     NUMBER-OF-PEOPLE = 9  ..
485
486     C5-1     =INTERIOR-WALL     AREA = 1611.0899  NEXT-TO ATTIC
487                                     CONSTRUCTION = CEIL_MAT2  ..
488
489     F5-1     =UNDERGROUND-FLOOR  AREA = 1611.0899
490                                     CONSTRUCTION = EXT_SLAB  ..
491
492
493     END  ..
494     COMPUTE  LOADS  ..
495
496
497
498     $===== SYSTEM DESCRIPTION =====
499
500     INPUT SYSTEMS  ..
501
502             SYSTEMS-REPORT  SUMMARY=(ALL-SUMMARY)
503             REPORT-FREQUENCY = HOURLY
504             HOURLY-DATA-SAVE = FORMATTED  ..

```

```

505
506
507 $ SYSTEMS SCHEDULES
508
509 FAN-1      =DAY-SCHEDULE      (1,6) (0) (7,19) (1) (20,24) (0) ..
510 FAN-2      =DAY-SCHEDULE      (1,24) (0) ..
511 FAN-3      =DAY-SCHEDULE      (1,24) (1) ..
512 FAN-4      =DAY-SCHEDULE      (1,6) (0) (7,23) (1) (24) (0) ..
513 FAN-5      =DAY-SCHEDULE      (1,8) (0) (9,17) (1) (18,24) (0) ..
514
515 FAN-WEEK   =WEEK-SCHEDULE      (WD) FAN-1 (WEH) FAN-2 ..
516 FAN-WEEK2  =WEEK-SCHEDULE      (WD) FAN-2 (WEH) FAN-2 ..
517 FAN-WEEK3  =WEEK-SCHEDULE      (WD) FAN-3 (WEH) FAN-3 ..
518
519
520 FAN-SCHED  =SCHEDULE            THRU DEC 31 FAN-WEEK ..
521 FAN-SCHED2 =SCHEDULE            THRU DEC 31 FAN-WEEK2 ..
522 FAN-SCHED3 =SCHEDULE            THRU DEC 31 FAN-WEEK3 ..
523
524
525 $ THERMOSTAT SET-POINTS FOR HEATING AND COOLING
526 $ SET TEMPERATURES CONVERTED TO IP UNITS FROM SI UNITS
527
528 HEAT-1     =DAY-SCHEDULE      (1,6) (60.01) (7) (69.98)
529                                     (8,19) (69.98) (20,24) (60.01) ..
530 HEAT-2     =DAY-SCHEDULE      (1,5) (60.01) (6) (64.04) (7) (68.0)
531                                     (8,17) (69.98) (18,24) (60.01) ..
532 HEAT-3     =DAY-SCHEDULE      (1,24) (60.01) ..
533 HEAT-4     =DAY-SCHEDULE      (1,24) (69.98) ..
534
535
536 HEAT-WEEK  =WEEK-SCHEDULE      (MON,FRI) HEAT-1 (SAT) HEAT-3 (SUN) HEAT-3
537                                     (HOL) HEAT-3 ..
538 HEAT-WEEK2 =WEEK-SCHEDULE      (MON,FRI) HEAT-3 (SAT) HEAT-3 (SUN) HEAT-3
539                                     (HOL) HEAT-3 ..
540 HEAT-WEEK3 =WEEK-SCHEDULE      (MON,FRI) HEAT-4 (SAT) HEAT-4 (SUN) HEAT-4
541                                     (HOL) HEAT-4 ..
542
543
544 HEAT-SCHED =SCHEDULE            THRU DEC 31 HEAT-WEEK ..
545 HEAT-SCHED2 =SCHEDULE          THRU DEC 31 HEAT-WEEK2 ..
546 HEAT-SCHED3 =SCHEDULE          THRU DEC 31 HEAT-WEEK3 ..
547
548
549 COOLOFF    =SCHEDULE            THRU DEC 31 (ALL) (1,24) (1) ..
550 HEATOFF    =SCHEDULE            THRU DEC 31 (ALL) (1,24) (1) ..
551
552
553 COOL-1     =DAY-SCHEDULE      (1,6) (84.99) (7) (75.00)
554                                     (8,18) (75.00) (19,24) (84.99) ..
555 COOL-2     =DAY-SCHEDULE      (1,5) (84.99) (6) (78.08) (7) (77.0)
556                                     (8,17) (75.00) (18,24) (84.99) ..
557 COOL-3     =DAY-SCHEDULE      (1,24) (84.99) ..
558 COOL-4     =DAY-SCHEDULE      (1,24) (75.00) ..
559
560
561 COOL-WEEK  =WEEK-SCHEDULE      (MON,FRI) COOL-1 (SAT) COOL-3 (SUN) COOL-3
562                                     (HOL) COOL-3 ..
563 COOL-WEEK2 =WEEK-SCHEDULE      (MON,FRI) COOL-3 (SAT) COOL-3 (SUN)
564 COOL-3
565                                     (HOL) COOL-3 ..
566 COOL-WEEK3 =WEEK-SCHEDULE      (MON,FRI) COOL-4 (SAT) COOL-4 (SUN)
567 COOL-4
568                                     (HOL) COOL-4 ..
569
569 COOL-SCHED =SCHEDULE            THRU DEC 31 COOL-WEEK ..
570 COOL-SCHED2 =SCHEDULE          THRU DEC 31 COOL-WEEK2
571 ..
571 COOL-SCHED3 =SCHEDULE          THRU DEC 31 COOL-WEEK3 ..
572
573
574 HVAC-HEAT  =SCHEDULE            THRU DEC 31 (ALL) (1,24) (1) ..

```

```

575 HVAC-COOL  =SCHEDULE      THRU DEC 31 (ALL) (1,24) (1)  ..
576
577 24HR-OFF   =SCHEDULE      THRU DEC 31 (ALL) (1,24) (0)  ..
578
579 DHW-SCHED  =SCHEDULE      THRU DEC 31 (ALL) (1,24) (1)  ..
580 DHWINLETSCH-1 =SCHEDULE    THRU DEC 31 (ALL) (1,24) (140) ..
581
582 INT-1      =DAY-SCHEDULE  (1,7) (0) (8) (0.35) (9) (0.69) (10)
(0.43)
583
584 (11) (0.37) (12) (0.43) (13) (0.58) (14) (0.48)
585 (15,16) (0.37) (17) (0.46) (18) (0.62)
(19) (0.12) (20,21) (0.04) (22,24) (0)
..
586 INT-2      =DAY-SCHEDULE  (1,7) (0) (8) (0.16) (9) (0.14) (10) (0.21)
587 (11) (0.18) (12) (0.25) (13) (0.21) (14) (0.13)
588 (15) (0.08) (16) (0.04) (17) (0.05)
589 (18) (0.06) (19,24) (0) ..
590 INT-3      =DAY-SCHEDULE  (1,24) (0) ..
591 INT-WEEK   =WEEK-SCHEDULE (MON,FRI) INT-3 (SAT) INT-3 (SUN) INT-3
592 (HOL) INT-3 ..
593 INT-SHED   = SCHEDULE     THRU DEC 31 INT-WEEK ..
594
595
596
597 $ SYSTEM DESCRIPTION
598
599 ZAIR       =ZONE-AIR      OA-CFM/PER= 17
600 EXHAUST-CFM = 0
601 EXHAUST-EFF = 0.75
602 EXHAUST-STATIC = 0 ..
603
604
605 CONTROL   = ZONE-CONTROL  DESIGN-HEAT-T = 70
606 DESIGN-COOL-T = 75
607 HEAT-TEMP-SCH = HEAT-SCHED
608 COOL-TEMP-SCH = COOL-SCHED
609 THERMOSTAT-TYPE =
PROPORTIONAL
610 THROTTLING-RANGE = 0.1
..
611
612
613 SPACE1-1  =ZONE          ZONE-AIR=ZAIR
614 SIZING-OPTION=ADJUST-LOADS
615 ZONE-CONTROL=CONTROL ..
616
617 SPACE2-1  =ZONE          LIKE SPACE1-1 ..
618 SPACE3-1  =ZONE          LIKE SPACE1-1 ..
619 SPACE4-1  =ZONE          LIKE SPACE1-1 ..
620 SPACE5-1  =ZONE          LIKE SPACE1-1 ..
621
622 ATTIC     =ZONE          ZONE-TYPE=UNCONDITIONED
..
623
624
625 S-CONT    =SYSTEM-CONTROL COOLING-SCHEDULE=
COOLOFF
626 HEATING-SCHEDULE=
HEATOFF
627 COOL-CONTROL = CONSTANT
628 PREHEAT-T = 44.6
629
MAX-SUPPLY-T=104
630
MIN-SUPPLY-T=55
..
631
632 S-AIR     =SYSTEM-AIR    MAX-OA-FRACTION =
1.0
633 OA-CONTROL = TEMP ..
634
635 S-FAN     =SYSTEM-FANS   FAN-SCHEDULE=FAN-SCHED5

```

```

636 FAN-CONTROL=
637 INLET
638 MOTOR-PLACEMENT =
639 IN-AIRFLOW
640 FAN-PLACEMENT =
641 DRAW-THROUGH
642
643 SUPPLY-EFF=0.55575
644
645 MAX-FAN-RATIO = 1.1
646 MIN-FAN-RATIO =
647 0.3
648
649 NIGHT-CYCLE-CTRL=STAY-OFF
650
651 SUPPLY-DELTA-T =
652 2.117
653 SUPPLY-KW = 0.000685
654 ..
655
656 $ COIL CURVE-FIT
657 HPACCoolCapFT =
658 CURVE-FIT
659
660 TYPE = BI-QUADRATIC
661 COEFFICIENTS = (0.766956,0.0107756,-0.0000414703,0.00134961,
662 -0.000261144,0.000457488) ..
663
664 HPACCoolCapFFF =
665 CURVE-FIT
666
667 TYPE = QUADRATIC
668 COEFFICIENTS = (0.8,0.2,0) ..
669
670 HPACCOOLEIRFT =
671 CURVE-FIT
672
673 TYPE = BI-QUADRATIC
674 COEFFICIENTS = (0.297145,0.0430933,-0.000748766,0.00597727,
675 0.000482112,-0.000956448) ..
676
677 HPACCOOLPLFFPLR =
678 CURVE-FIT
679
680 TYPE = QUADRATIC
681 COEFFICIENTS = (0.85,0.15,0) ..
682
683 S-EQUIP =SYSTEM-EQUIPMENT COOL-CAP-FT = SDL-C3
684 COOLING-EIR = 0.242745131
685 COOL-EIR-FT =
686 SDL-C13
687 COOL-EIR-FPLR = SDL-C18
688 COOL-SH-FT =SDL-C23
689 COIL-BF-FT = HPACCoolCapFT
690 COIL-BF-FCFM = HPACCoolCapFFF
691 COIL-BF-FPLR = HPACCOOLPLFFPLR
692
693 COIL-BF=0.19
694
695 COOL-FT-MIN=
696 70
697 HEAT-CAP-FT =
698 SDL-C55
699 HEATING-EIR =
700 0.29751543
701 HEAT-EIR-FT =
702 SDL-C60
703 HEAT-EIR-FPLR =
704 SDL-C65
705 DEFROST-FRAC-FT =
706 HPACCOOLEIRFT
707 OUTSIDE-FAN-T = 45
708 OUTSIDE-FAN-MODE =
709 INTERMITTENT
710 COMPRESSOR-TYPE =
711 SINGLE-SPEED
712 RATED-CCAP-FCFM = SDL-C78
713 RATED-SH-FCFM=

```

```

684          SDL-C85
685          RATED-CEIR-FCFM= SDL-C93
686          RATED-HCAP-FCFM=
687          SDL-C100
688          CRANKCASE-HEAT= 0.05
689          CRANKCASE-MAX-T= 39.92
690          ..
691          SYST-1      =SYSTEM      SYSTEM-TYPE=
692          PVAVS
693          SYSTEM-CONTROL= S-CONT
694          SYSTEM-FANS= S-FAN
695          SYSTEM-TERMINAL= S-TERM
696          SYSTEM-EQUIPMENT=
697          S-EQUIP
698          HEAT-SOURCE=
699          HEAT-PUMP
700          PREHEAT-SOURCE=
701          HEAT-PUMP
702          RETURN-AIR-PATH= DIRECT
703          SIZING-OPTION =
704          NON-COINCIDENT
705          ZONE-NAMES= (SPACE5-1,SPACE1-1,SPACE2-1
706          SPACE3-1,SPACE4-1,ATTIC)
707          ..
708          HP-1      = PLANT-ASSIGNMENT SYSTEM-NAMES = (SYST-1)
709          HP-LOOP-HEATING = FROM-SYSTEMS
710          HP-LOOP-COOLING = FROM-SYSTEMS
711          DHW-SIZE      = 40
712          DHW-GAL/MIN  =
713          0.0486
714          DHW-SCH      = DHW-SCHED
715          DHW-INLET-T-SCH = DHWINLETSCH-1
716          DHW-SUPPLY-T =
717          131
718          DHW-TYPE     = ELECTRIC
719          DHW-EIR      = 1
720          DHW-EIR-FT   = DHWHPEIRFT
721          DHW-HEAT-RATE-FT = DHWHPCAPFT
722          DHW-EIR-FPLR = DHWGEIRFPLR
723          DHW-PUMP-ELEC = 0
724          MAX-FLUID-T  = 140
725          MIN-FLUID-T  = 50
726          FLUID-VOLUME = 15
727          ..
728          $===== HOURLY-REPORT FOR SYSTEM
729          =====
730          $ HOURLY-REPORT FOR SYSTEM PART
731          HRSCH-2      = SCHEDULE
732          THRU DEC 31 (ALL) (1,24) (1) ..
733          S1_ZT        = REPORT-BLOCK
734          VARIABLE-TYPE=SPACE1-1
735          VARIABLE-LIST=(6,14)
736          ..
737          S2_ZT        = REPORT-BLOCK
738          VARIABLE-TYPE=SPACE2-1
739          VARIABLE-LIST=(6,14)
740          ..
741          S3_ZT        = REPORT-BLOCK
742          VARIABLE-TYPE=SPACE3-1

```

```

738             VARIABLE-LIST=(6,14) ..
739
740 S4_ZT         = REPORT-BLOCK
741             VARIABLE-TYPE=SPACE4-1
742             VARIABLE-LIST=(6,14) ..
743
744 S5_ZT         = REPORT-BLOCK
745             VARIABLE-TYPE=SPACE5-1
746             VARIABLE-LIST=(6,14)
              ..
747
748 SYS1          = REPORT-BLOCK
749             VARIABLE-TYPE=SYST-1
750             VARIABLE-LIST=(1,2) ..
751
752 PPRT1        = HOURLY-REPORT
753             REPORT-SCHEDULE = HRSCH-2
754             REPORT-BLOCK = (S1_ZT,S2_ZT,S3_ZT,S4_ZT,S5_ZT,SYST1) ..
755
756 $=====
757
758
759
760 END          ..
761 COMPUTE SYSTEMS ..
762
763
764 INPUT PLANT ..
765
766             PLANT-REPORT SUMMARY=(ALL-SUMMARY)
767             REPORT-FREQUENCY = HOURLY
768             HOURLY-DATA-SAVE = FORMATTED ..
769
770 $===== HOURLY-REPORT FOR PLANT
771 =====
772 HRSCH-3      = SCHEDULE
773             THRU DEC 31 (ALL) (1,24) (1) ..
774
775 PLT          = REPORT-BLOCK
776             VARIABLE-TYPE=PLANT
777             VARIABLE-LIST=(3) ..
778
779 ENDU         = REPORT-BLOCK
780             VARIABLE-TYPE=END-USE
781             VARIABLE-LIST=(1,3,5,6,9)
              ..
782
783 PPRT1        = HOURLY-REPORT
784             REPORT-SCHEDULE = HRSCH-3
785             REPORT-BLOCK = (PLT,ENDU) ..
786
787 $=====
788
789
790 END          ..
791 COMPUTE PLANT ..
792
793
794
795 STOP        ..
796

```


2.3 Chicago, IL: Thermal Zoning Models

2.3.1 Reference Model 1: Single-Zone Model in Chicago, IL (PSZ System)

In this section the DOE-2 input file for "Case 1: Five-Zone Model in Chicago, IL" is described.

```

1  $===== SIMULATION ZONING =====
2
3  INPUT LOADS ..
4
5  TITLE          LINE-1 *SAMPLE PROVIDED BY PROF.JEFF HABERL*
6                LINE-2 *CHICAGO, TX, CLIMATE ZONE 4A*
7                LINE-3 *ASHRAE 90.1-2016 REQUIREMENTS SATISFIED*
8                LINE-4 *STUDY FOR BUILDING OCCUPANCY PROFILE ANALYSIS* ..
9
10             RUN-PERIOD      JAN 1 2019 THRU DEC 31 2019  ..
11
12             ABORT           ERRORS ..
13             DIAGNOSTIC     WARNINGS ..
14             LOADS-REPORT   SUMMARY = (ALL-SUMMARY)
15                             REPORT-FREQUENCY = HOURLY
16                             HOURLY-DATA-SAVE = FORMATTED
17                             VERIFICATION = (ALL-VERIFICATION) ..
18
19             BUILDING-LOCATION LATITUDE=41.98
20                             LONGITUDE=87.92
21                             GROUND-T = (67.838, 67.604, 67.604, 67.838,
22                             68.18, 72.05, 73.184, 73.526, 73.634, 69.944,
23                             68.954, 68.342)
24                             DAYLIGHT-SAVINGS = NO
25                             ALTITUDE=659.45
26                             TIME-ZONE=6
27                             AZIMUTH=0.0  ..
28
29  $ BUILDING DESCRIPTION
30
31  $===== BUILDING CONSTRUCTION =====
32
33
34  $ CONSTRUCTION AND GLASS-TYPES
35
36  $ MATERIAL PROPERTY (IP UNITS)
37  $ ALL VALUES CONVERTED FROM SI UNITS IN PNNL SMALL OFFICE MODEL FOR 90.1-2016
38  $ ROOF AND CEILING PROPERTY
39  ROOF_BUIL      = MAT          THICKNESS = 0.03116798
40                                     CONDUCTIVITY = 0.092446272
41                                     DENSITY = 69.9193264
42                                     SPECIFIC-HEAT = 0.348715014  ..
43
44  ROOF_INS_2     = MAT          RESISTANCE = 45.98476874  ..
45
46  ROOF_SUR_1     = MAT          THICKNESS = 0.002624672
47                                     CONDUCTIVITY = 26.16229498
48                                     DENSITY = 488.4364373
49                                     SPECIFIC-HEAT = 0.11942295  ..
50
51  ROOF_ASPHT     = MAT          THICKNESS = 0.010498688
52                                     CONDUCTIVITY = 0.023111568
53                                     DENSITY = 69.9193264
54                                     SPECIFIC-HEAT = 0.300945834  ..
55
56  ROOF_WOOD      = MAT          THICKNESS = 0.052165356
57                                     CONDUCTIVITY = 0.069334704
58                                     DENSITY = 33.96081568
59                                     SPECIFIC-HEAT = 0.289003539  ..
60
61
62  $ SLAB PROPERTY
63  SLAB_CONC200   = MAT          THICKNESS = 0.666666688
64                                     CONDUCTIVITY = 1.334693052
65                                     DENSITY = 144.9577463
66                                     SPECIFIC-HEAT = 0.198719789  ..
67
68  SLAB_CONC100   = MAT          THICKNESS = 0.333333344
69                                     CONDUCTIVITY = 1.334693052
70                                     DENSITY = 144.9577463
71                                     SPECIFIC-HEAT = 0.198719789  ..
72
73  SLAB_CARP      = MAT          RESISTANCE = 1.22923033  ..

```

```

74
75
76 $ WALL PROPERTY
77 WALL_STU      = MAT          THICKNESS = 0.08333336
78                                     CONDUCTIVITY = 0.416008224
79                                     DENSITY = 115.8663123
80                                     SPECIFIC-HEAT = 0.200630556 ..
81
82 WALL_GYP1     = MAT          THICKNESS = 0.052165356
83                                     CONDUCTIVITY = 0.092446272
84                                     DENSITY = 49.942376
85                                     SPECIFIC-HEAT = 0.260342031 ..
86
87 WALL_GYP2     = MAT          THICKNESS = 0.041666668
88                                     CONDUCTIVITY = 0.092446272
89                                     DENSITY = 49.942376
90                                     SPECIFIC-HEAT = 0.260342031 ..
91
92 WALL_INS_2    = MAT          RESISTANCE = 17.42897129 ..
93
94
95 $ WINDOW PROPERTY
96 WIN_GLS3      = GLASS-TYPE   GLASS-CONDUCTANCE = 0.3954
97                                     VIS-TRANS = 0.452
98                                     SHADING-COEF =
99                                     0.41954023
100                                    PANES = 2 ..
101
102 DOOR1         = GLASS-TYPE   GLASS-CONDUCTANCE = 0.370
103                                     SHADING-COEF = 0.7 ..
104
105 AIR-LAYER     = CONSTRUCTION U = 1.11 ..
106
107
108 $ MATERIAL LAYERS
109 ATTIC-R1     =LAYERS =MAT=(AR02,PW04) ..
110
111 ATTIC-R2     =LAYERS =MAT=(PW04) ..
112
113 ROOF_1       =LAYERS =MAT=(ROOF_INS_2,GP02) ..
114 EX_SLAB_1    =LAYERS =MAT=(SLAB_CONC200,CP02) ..
115 EX_WALL_1    =LAYERS =MAT=(SC01,GP02,WALL_INS_2,GP02) ..
116 IN_WALL_1    =LAYERS =MAT=(GP01,GP01) ..
117 IN_SLAB_1    =LAYERS =MAT=(SLAB_CONC100,CP02) ..
118 CEIL_MAT1    =LAYERS =MAT=(AC02,GP01) ..
119
120
121 $ MATERIAL CONSTRUCTION
122 EXT_SLAB     =CONSTRUCTION   LAYERS = EX_SLAB_1
123                                     ABSORPTANCE = 0.7 ..
124 NONRES_EXT_WALL =CONSTRUCTION LAYERS = EX_WALL_1
125                                     ABSORPTANCE = 0.7 ..
126 INT_WALL     =CONSTRUCTION   LAYERS = IN_WALL_1
127                                     ABSORPTANCE = 0.7 ..
128 CEIL_MAT2    =CONSTRUCTION   LAYERS = ROOF_1
129                                     ABSORPTANCE = 0.7 ..
130 ATTIC-ROOF   =CONSTRUCTION   LAYERS = ATTIC-R1
131                                     ABSORPTANCE = 0.7 ..
132 ATTIC-SOFFIT =CONSTRUCTION   LAYERS = ATTIC-R2
133                                     ABSORPTANCE = 0.7 ..
134 DOOR2        =CONSTRUCTION   U = 1.426492621
135                                     ABSORPTANCE = 0.7 ..
136
137 $ OCCUPANCY SCHEDULE
138 OC-1         =DAY-SCHEDULE   (1,6) (0.0)
139                                     (7) (0.11)
140                                     (8) (0.21)
141                                     (9,12) (1.0)
142                                     (13) (0.53)
143                                     (14,17) (1.0)
144                                     (18) (0.32)
145                                     (19,22) (0.11)

```

```

146 (23) (0.05)
147 (24) (0.0) ..
148
149 OC-2 =DAY-SCHEDULE (1,6) (0.0)
150 (7,8) (0.1)
151 (9,12) (0.3)
152 (13,17) (0.1)
153 (18,19) (0.05)
154 (20,24) (0.0) ..
155
156 OC-3 =DAY-SCHEDULE (1,6) (0.0)
157 (7,18) (0.05)
158 (19,24) (0.0) ..
159
160 OC-4 =DAY-SCHEDULE (1,24) (0.0) ..
161 OC-5 =DAY-SCHEDULE (1,24) (1.0) ..
162
163
164 OC-WEEK =WEEK-SCHEDULE (WD) OC-1 (SAT) OC-4 (SUN) OC-4 (HOL) OC-4 ..
165 OC-WEEK2 =WEEK-SCHEDULE (WD) OC-4 (SAT) OC-4 (SUN) OC-4 (HOL) OC-4 ..
166 OC-WEEK3 =WEEK-SCHEDULE (WD) OC-5 (SAT) OC-5 (SUN) OC-5 (HOL) OC-5 ..
167
168 OCCUPY-1 =SCHEDULE THRU DEC 31 OC-WEEK ..
169 OCCUPY-2 =SCHEDULE THRU DEC 31 OC-WEEK2 ..
170 OCCUPY-3 =SCHEDULE THRU DEC 31 OC-WEEK3 ..
171
172
173 $ LIGHTING SCHEDULE
174
175 LT-1 =DAY-SCHEDULE (1,5) (0.18)
176 (6,7) (0.23)
177 (8) (0.42)
178 (9,12) (0.9)
179 (13) (0.8)
180 (14,17) (0.9)
181 (18) (0.61)
182 (19,20) (0.42)
183 (21,22) (0.32)
184 (23) (0.23)
185 (24) (0.18) ..
186
187 LT-0 =DAY-SCHEDULE (1,6) (0.0)
188 (7) (0.11)
189 (8) (0.21)
190 (9,12) (1.0)
191 (13) (0.53)
192 (14,17) (1.0)
193 (18) (0.32)
194 (19,22) (0.11)
195 (23) (0.05)
196 (24) (0.0) ..
197
198 LT-2 =DAY-SCHEDULE (1,6) (0.05)
199 (7,8) (0.1)
200 (9,12) (0.3)
201 (13,17) (0.15)
202 (18,24) (0.05) ..
203
204 LT-3 =DAY-SCHEDULE (1,24) (0.18) ..
205 LT-4 =DAY-SCHEDULE (1,24) (0.0) ..
206 LT-5 =DAY-SCHEDULE (1,24) (1.0) ..
207
208
209 LT-WEEK =WEEK-SCHEDULE (WD) LT-1 (SAT) LT-3 (SUN) LT-3 (HOL) LT-3 ..
210 LT-WEEK2 =WEEK-SCHEDULE (WD) LT-3 (SAT) LT-3 (SUN) LT-3 (HOL) LT-3 ..
211 LT-WEEK3 =WEEK-SCHEDULE (WD) LT-5 (SAT) LT-5 (SUN) LT-5 (HOL) LT-5 ..
212
213 LIGHTS-1 =SCHEDULE THRU DEC 31 LT-WEEK ..
214 LIGHTS-2 =SCHEDULE THRU DEC 31 LT-WEEK2 ..
215 LIGHTS-3 =SCHEDULE THRU DEC 31 LT-WEEK3 ..
216
217
218 $ OFFICE EQUIPMENT SCHEDULE

```

```

219 EQ-1 =DAY-SCHEDULE (1,5) (0.5)
220 (6,12) (1.0)
221 (13) (0.94)
222 (14,17) (1.0)
223 (18) (0.5)
224 (19,24) (0.2) ..
225
226 EQ-0 =DAY-SCHEDULE (1,6) (0.0)
227 (7) (0.11)
228 (8) (0.21)
229 (9,12) (1.0)
230 (13) (0.53)
231 (14,17) (1.0)
232 (18) (0.32)
233 (19,22) (0.11)
234 (23) (0.05)
235 (24) (0.0) ..
236
237 EQ-2 =DAY-SCHEDULE (1,6) (0.3)
238 (7,8) (0.4)
239 (9,12) (0.5)
240 (13,17) (0.35)
241 (18,24) (0.3) ..
242
243 EQ-3 =DAY-SCHEDULE (1,24) (0.2) ..
244 EQ-4 =DAY-SCHEDULE (1,24) (0.0) ..
245 EQ-5 =DAY-SCHEDULE (1,24) (1.0) ..
246
247
248 EQ-WEEK =WEEK-SCHEDULE (WD) EQ-1 (SAT) EQ-3 (SUN) EQ-3 (HOL) EQ-3 ..
249 EQ-WEEK2 =WEEK-SCHEDULE (WD) EQ-3 (SAT) EQ-3 (SUN) EQ-3 (HOL) EQ-3 ..
250 EQ-WEEK3 =WEEK-SCHEDULE (WD) EQ-5 (SAT) EQ-5 (SUN) EQ-5 (HOL) EQ-5 ..
251
252
253 EQUIP-1 =SCHEDULE THRU DEC 31 EQ-WEEK ..
254 EQUIP-2 =SCHEDULE THRU DEC 31 EQ-WEEK2 ..
255 EQUIP-3 =SCHEDULE THRU DEC 31 EQ-WEEK3 ..
256
257
258 $ INFILTRATION SCHEDULE
259 IF-1 =DAY-SCHEDULE (1,6) (1.0)
260 (7,19) (0.25)
261 (20,24) (1.0) ..
262
263 IF-2 =DAY-SCHEDULE (1,7) (1.0)
264 (8,18) (0.25)
265 (19,24) (1.0) ..
266
267 IF-3 =DAY-SCHEDULE (1,24) (0.0) ..
268 IF-4 =DAY-SCHEDULE (1,24) (1.0) ..
269 IF-5 =DAY-SCHEDULE (1,24) (0.25) ..
270
271
272 IF-WEEK =WEEK-SCHEDULE (WD) IF-1 (SAT) IF-2 (SUN) IF-4 (HOL) IF-4 ..
273 IF-WEEK2 =WEEK-SCHEDULE (WD) IF-4 (SAT) IF-4 (SUN) IF-4 (HOL) IF-4 ..
274 IF-WEEK3 =WEEK-SCHEDULE (WD) IF-5 (SAT) IF-5 (SUN) IF-5 (HOL) IF-5 ..
275
276 INFIL-SCH =SCHEDULE THRU DEC 31 IF-WEEK ..
277 INFIL-SCH2 =SCHEDULE THRU DEC 31 IF-WEEK2 ..
278 INFIL-SCH3 =SCHEDULE THRU DEC 31 IF-WEEK3 ..
279
280
281 $===== SPACE DEFAULTS & DESCRIPTION =====
282
283
284 $ SET DEFAULT VALUE
285
286 SET-DEFAULT FOR SPACE FLOOR-WEIGHT = 0 ..
287 SET-DEFAULT FOR WINDOW HEIGHT=5.0
288 GLASS-TYPE=WIN_GLS3 Y=1 ..
289 SET-DEFAULT FOR EXTERIOR-WALL CONSTRUCTION=NONRES_EXT_WALL ..
290
291

```

```

292 $ GENERAL SPACE DEFINITION
293
294 OFFICE      =SPACE-CONDITIONS  PEOPLE-SCHEDULE      =OCCUPY-1
295                                NUMBER-OF-PEOPLE      =31
296                                PEOPLE-HEAT-GAIN      =450
297                                LIGHTING-SCHEDULE     =LIGHTS-1
298                                LIGHTING-W/SQFT       = 0.79
299                                EQUIP-SCHEDULE        = EQUIP-1
300                                EQUIPMENT-W/SQFT      = 0.63
301                                INF-METHOD          = AIR-CHANGE
302                                AIR-CHANGES/HR       = 0.0
303                                INF-SCHEDULE          =INFIL-SCH ..
304
305
306                $ SPECIFIC SPACE DETAILS
307
308 $ ATTIC
309 ATTIC-SC    = SPACE-CONDITIONS
310            ZONE-TYPE = UNCONDITIONED
311            FLOOR-WEIGHT = 0 ..                $ CUSTOM WEITING FACTOR
312
313 ATTIC      = SPACE      S-C = ATTIC-SC  AREA = 6113.686  VOLUME = 24533.31
314            X = 0  Y = 0  Z = 0  AZ = 0 ..
315 N-ROOF = POLYGON
316        (92.81,62.53) (-1.97,62.53) (30.28,32.03) (60.56,32.03) ..
317 S-ROOF = POLYGON
318        (-1.97,-1.97) (92.81,-1.97) (60.56,32.03) (30.28,32.03) ..
319 E-GABLE = POLYGON
320        (0,0) (64.5,0) (32.25,34) ..
321 W-GABLE = POLYGON
322        (-1.97,62.53,10) (-1.97,-1.97,10) (30.28,30.28,20.77) ..
323
324
325
326 $ ROOF RAISED
327 N-ROOF-EXT = ROOF      CONSTRUCTION = ATTIC-ROOF
328                                POLYGON = S-ROOF
329                                TILT =18.5, AZ = 0,
330                                X= 90.84 Y = 60.56 Z = 10.0 ..
331
332 S-ROOF-EXT = ROOF      CONSTRUCTION = ATTIC-ROOF
333                                POLYGON = S-ROOF
334                                TILT =18.5, AZ = 180, Z = 10.0 ..
335
336 E-GABLE-EXT = ROOF     CONSTRUCTION = ATTIC-ROOF
337                                POLYGON = E-GABLE
338                                TILT =18.2, AZ = 90
339                                X = 92.81 Y = -1.97 Z = 10.0 ..
340
341 W-GABLE-EXT = ROOF     CONSTRUCTION = ATTIC-ROOF
342                                POLYGON = E-GABLE
343                                TILT =18.2, AZ = 270
344                                X = -1.97 Y = 62.53 Z = 10.0 ..
345
346
347 N-ROOF-SOFFIT = BUILDING-SHADE  HEIGHT = 1.97  WIDTH = 94.78
348                                X=-1.97 Y=60.6 Z=10
349                                TRANSMITTANCE = 0.0
350                                AZIMUTH = 180  TILT = 180 ..
351 S-ROOF-SOFFIT = BUILDING-SHADE  HEIGHT = 1.97  WIDTH =
352        94.78
353                                X=-1.97 Y=0 Z=10
354                                TRANSMITTANCE = 0.0
355                                AZIMUTH = 180  TILT = 180 ..
356 E-ROOF-SOFFIT = BUILDING-SHADE  HEIGHT = 1.97  WIDTH =
357        60.56
358                                X=90.85 Y=0 Z=10
359                                TRANSMITTANCE = 0.0
360                                AZIMUTH = 90  TILT = 180 ..
361 W-ROOF-SOFFIT = BUILDING-SHADE  HEIGHT = 1.97  WIDTH =
362        60.56
363                                X=0 Y=0 Z=10
364                                TRANSMITTANCE = 0.0

```

```

362                                AZIMUTH = 90  TILT = 180  ..
363
364
365
366  SPACE1-1  =SPACE                SPACE-CONDITIONS = OFFICE
367                                AREA = 1221.28925  VOLUME = 12221.4264
368                                NUMBER-OF-PEOPLE = 7  ..
369  FRONT-1   =EXTERIOR-WALL        HEIGHT = 10  WIDTH = 90.8
370                                X=0  Y=0  Z=0  AZIMUTH = 180  ..
371
372  WF-1      =WINDOW                WIDTH = 6  X = 4.56  Y = 2.95  ..
373  WF-2      =WINDOW                WIDTH = 6  X = 19.72  Y = 2.95  ..
374  WF-3      =WINDOW                WIDTH = 6  X = 34.84  Y = 2.95  ..
375  WF-4      =WINDOW                WIDTH = 6  X = 50.00  Y = 2.95  ..
376  WF-5      =WINDOW                WIDTH = 6  X = 65.12  Y = 2.95  ..
377  WF-6      =WINDOW                WIDTH = 6  X = 80.28  Y = 2.95  ..
378  DF-1      =WINDOW                WIDTH = 6  HEIGHT = 7
379                                X = 42.42  Y = 0
380                                GLASS-TYPE=WIN_GLS3  ..
381
382  C1-1      =INTERIOR-WALL        AREA = 1221.28925  NEXT-TO ATTIC
383                                CONSTRUCTION = CEIL_MAT2  ..
384
385  F1-1      =UNDERGROUND-FLOOR    AREA = 1221.28925
386                                CONSTRUCTION = EXT_SLAB  ..
387
388  SB12      =INTERIOR-WALL        AREA=231.931  NEXT-TO SPACE2-1
389                                CONSTRUCTION = INT_WALL  ..
390
391  SB14      =INTERIOR-WALL        LIKE SB12  NEXT-TO SPACE4-1  ..
392  SB15      =INTERIOR-WALL        AREA 580  NEXT-TO SPACE5-1
393                                CONSTRUCTION = INT_WALL  ..
394
395  SPACE2-1  =SPACE                SPACE-CONDITIONS = OFFICE
396                                AREA = 724.4845  VOLUME = 7249.7832
397                                NUMBER-OF-PEOPLE = 4  ..
398
399  RIGHT-1   =EXTERIOR-WALL        HEIGHT = 10  WIDTH = 60.5
400                                X=90.8  Y=0  Z=0  AZIMUTH = 90  ..
401
402  WR-1      =WINDOW                WIDTH = 6  X = 4.56  Y = 2.95  ..
403  WR-2      =WINDOW                WIDTH = 6  X = 19.72  Y = 2.95  ..
404  WR-3      =WINDOW                WIDTH = 6  X = 34.84  Y = 2.95  ..
405  WR-4      =WINDOW                WIDTH = 6  X = 50.00  Y = 2.95  ..
406
407  C2-1      =INTERIOR-WALL        AREA = 724.4845  NEXT-TO ATTIC
408                                CONSTRUCTION = CEIL_MAT2  ..
409
410  F2-1      =UNDERGROUND-FLOOR    AREA = 724.4845
411                                CONSTRUCTION = EXT_SLAB  ..
412
413  SB23      =INTERIOR-WALL        AREA = 231.931  NEXT-TO SPACE3-1
414                                CONSTRUCTION = INT_WALL  ..
415
416  SB25      =INTERIOR-WALL        AREA = 277  NEXT-TO SPACE5-1
417                                CONSTRUCTION = INT_WALL  ..
418
419  SPACE3-1  =SPACE                SPACE-CONDITIONS = OFFICE
420                                AREA = 1221.28925  VOLUME = 12221.4264
421                                NUMBER-OF-PEOPLE = 7  ..
422
423  BACK-1    =EXTERIOR-WALL        HEIGHT = 10  WIDTH = 90.8
424                                X=90.8  Y=60.5  Z=0  AZIMUTH = 0  ..
425
426  WB-1      =WINDOW                WIDTH = 6  X = 4.56  Y = 2.95  ..
427  WB-2      =WINDOW                WIDTH = 6  X = 19.72  Y = 2.95  ..
428  WB-3      =WINDOW                WIDTH = 6  X = 34.84  Y = 2.95  ..
429  WB-4      =WINDOW                WIDTH = 6  X = 50.00  Y = 2.95  ..
430  WB-5      =WINDOW                WIDTH = 6  X = 65.12  Y = 2.95  ..
431  WB-6      =WINDOW                WIDTH = 6  X = 80.28  Y = 2.95  ..
432  DB-1      =DOOR                  WIDTH = 3  HEIGHT = 7
433                                X = 28.08  Y = 0
434                                CONSTRUCTION = DOOR2  ..

```

```

435     DB-2     =DOOR           WIDTH = 3  HEIGHT = 7
436                                     X = 41.92 Y = 0
437                                     CONSTRUCTION = DOOR2  ..
438
439     C3-1     =INTERIOR-WALL   AREA = 1221.28925 NEXT-TO ATTIC
440                                     CONSTRUCTION = CEIL_MAT2  ..
441
442     F3-1     =UNDERGROUND-FLOOR AREA = 1221.28925
443                                     CONSTRUCTION = EXT_SLAB  ..
444
445     SB34     =INTERIOR-WALL   AREA = 231.931 NEXT-TO SPACE4-1
446                                     CONSTRUCTION = INT_WALL  ..
447
448     SB35     =INTERIOR-WALL   AREA = 580 NEXT-TO SPACES5-1
449                                     CONSTRUCTION = INT_WALL  ..
450
451     SPACE4-1 =SPACE           SPACE-CONDITIONS = OFFICE
452                                     AREA = 724.4845 VOLUME = 7249.7832
453                                     NUMBER-OF-PEOPLE = 4  ..
454
455     LEFT-1   =EXTERIOR-WALL   HEIGHT = 10  WIDTH = 60.5
456                                     X=0  Y=60.5  Z=0  AZIMUTH = 270  ..
457
458     WL-1     =WINDOW           WIDTH = 6  X = 4.56  Y = 2.95  ..
459     WL-2     =WINDOW           WIDTH = 6  X = 19.72 Y = 2.95  ..
460     WL-3     =WINDOW           WIDTH = 6  X = 34.84 Y = 2.95  ..
461     WL-4     =WINDOW           WIDTH = 6  X = 50.00 Y = 2.95  ..
462
463     C4-1     =INTERIOR-WALL   AREA = 724.4845 NEXT-TO ATTIC
464                                     CONSTRUCTION = CEIL_MAT2  ..
465
466     F4-1     =UNDERGROUND-FLOOR AREA = 724.4845
467                                     CONSTRUCTION = EXT_SLAB  ..
468
469     SB45     =INTERIOR-WALL   AREA = 277 NEXT-TO SPACES5-1
470                                     CONSTRUCTION = INT_WALL  ..
471
472     SPACE5-1 =SPACE           SPACE-CONDITIONS = OFFICE
473                                     AREA = 1611.0899 VOLUME = 16122.1672
474                                     NUMBER-OF-PEOPLE = 9  ..
475
476     C5-1     =INTERIOR-WALL   AREA = 1611.0899 NEXT-TO ATTIC
477                                     CONSTRUCTION = CEIL_MAT2  ..
478
479     F5-1     =UNDERGROUND-FLOOR AREA = 1611.0899
480                                     CONSTRUCTION = EXT_SLAB .
481
482     END ..
483     COMPUTE LOADS ..
484
485
486
487     $===== SYSTEM DESCRIPTION =====
488
489     INPUT SYSTEMS ..
490
491             SYSTEMS-REPORT SUMMARY=(ALL-SUMMARY)
492             REPORT-FREQUENCY = HOURLY
493             HOURLY-DATA-SAVE = FORMATTED ..
494
495
496     $ SYSTEMS SCHEDULES
497
498     FAN-1     =DAY-SCHEDULE   (1,6) (0) (7,19) (1) (20,24) (0)  ..
499     FAN-2     =DAY-SCHEDULE   (1,24) (0)  ..
500     FAN-3     =DAY-SCHEDULE   (1,24) (1)  ..
501     FAN-4     =DAY-SCHEDULE   (1,6) (0) (7,23) (1) (24) (0)  ..
502     FAN-5     =DAY-SCHEDULE   (1,8) (0) (9,17) (1) (18,24) (0)  ..
503
504     FAN-WEEK  =WEEK-SCHEDULE  (WD) FAN-1 (WEH) FAN-2  ..
505     FAN-WEEK2 =WEEK-SCHEDULE  (WD) FAN-2 (WEH) FAN-2  ..
506     FAN-WEEK3 =WEEK-SCHEDULE  (WD) FAN-3 (WEH) FAN-3  ..
507

```

```

508 FAN-SCHED      =SCHEDULE          THRU DEC 31  FAN-WEEK
..
509 FAN-SCHED2    =SCHEDULE          THRU DEC 31  FAN-WEEK2 ..
510 FAN-SCHED3    =SCHEDULE          THRU DEC 31  FAN-WEEK3
..
511
512
513 $ THERMOSTAT SET-POINTS FOR HEATING AND COOLING
514 $ SET TEMPERATURES CONVERTED TO IP UNITS FROM SI UNITS
515
516 HEAT-1        =DAY-SCHEDULE    (1,6) (60.01) (7) (69.98)
517              (8,19) (69.98) (20,24) (60.01)
..
518 HEAT-2        =DAY-SCHEDULE    (1,5) (60.01) (6) (64.04) (7) (68.0)
519              (8,17) (69.98) (18,24) (60.01) ..
520 HEAT-3        =DAY-SCHEDULE    (1,24) (60.01) ..
521 HEAT-4        =DAY-SCHEDULE    (1,24) (69.98) ..
522
523 HEAT-WEEK     =WEEK-SCHEDULE    (MON,FRI) HEAT-1 (SAT) HEAT-3 (SUN) HEAT-3
524              (HOL) HEAT-3 ..
525 HEAT-WEEK2    =WEEK-SCHEDULE    (MON,FRI) HEAT-3 (SAT) HEAT-3 (SUN)
HEAT-3
526              (HOL) HEAT-3 ..
527 HEAT-WEEK3    =WEEK-SCHEDULE    (MON,FRI) HEAT-4 (SAT) HEAT-4 (SUN)
HEAT-4
528              (HOL) HEAT-4 ..
529
530 HEAT-SCHED    =SCHEDULE          THRU DEC 31  HEAT-WEEK
..
531 HEAT-SCHED2   =SCHEDULE          THRU DEC 31  HEAT-WEEK2
..
532 HEAT-SCHED3   =SCHEDULE          THRU DEC 31  HEAT-WEEK3
..
533
534
535 COOLOFF       =SCHEDULE          THRU DEC 31  (ALL) (1,24) (1)
..
536 HEATOFF       =SCHEDULE          THRU DEC 31  (ALL) (1,24) (1)
..
537
538
539 COOL-1        =DAY-SCHEDULE    (1,6) (84.99) (7)
(75.00)
540              (8,18) (75.00) (19,24) (84.99)
..
541 COOL-2        =DAY-SCHEDULE    (1,5) (84.99) (6) (78.08) (7) (77.0)
542              (8,17) (75.00) (18,24) (84.99) ..
543 COOL-3        =DAY-SCHEDULE    (1,24) (84.99) ..
544 COOL-4        =DAY-SCHEDULE    (1,24) (75.00) ..
545
546 COOL-WEEK     =WEEK-SCHEDULE    (MON,FRI) COOL-1 (SAT) COOL-3 (SUN) COOL-3
547              (HOL) COOL-3 ..
548 COOL-WEEK2    =WEEK-SCHEDULE    (MON,FRI) COOL-3 (SAT) COOL-3 (SUN)
COOL-3
549              (HOL) COOL-3 ..
550 COOL-WEEK3    =WEEK-SCHEDULE    (MON,FRI) COOL-4 (SAT) COOL-4 (SUN)
COOL-4
551              (HOL) COOL-4 ..
552
553 COOL-SCHED    =SCHEDULE          THRU DEC 31  COOL-WEEK
..
554 COOL-SCHED2   =SCHEDULE          THRU DEC 31  COOL-WEEK2
..
555 COOL-SCHED3   =SCHEDULE          THRU DEC 31  COOL-WEEK3
..
556
557
558 HVAC-HEAT     =SCHEDULE          THRU DEC 31  (ALL) (1,24) (1) ..
559 HVAC-COOL     =SCHEDULE          THRU DEC 31  (ALL) (1,24) (1)
..
560
561 24HR-OFF      =SCHEDULE          THRU DEC 31  (ALL) (1,24) (0)
..

```



```

562
563 DHW-SCHED =SCHEDULE THRU DEC 31 (ALL) (1,24) (1)
..
564 DHWINLETSCH-1 =SCHEDULE THRU DEC 31 (ALL) (1,24) (140)
..
565
566 INT-1 =DAY-SCHEDULE (1,7) (0) (8) (0.35) (9) (0.69) (10)
(0.43)
567 (11) (0.37) (12) (0.43) (13) (0.58) (14) (0.48)
568 (15,16) (0.37) (17) (0.46) (18) (0.62)
569 (19) (0.12) (20,21) (0.04) (22,24) (0)
..
570 INT-2 =DAY-SCHEDULE (1,7) (0) (8) (0.16) (9) (0.14) (10) (0.21)
571 (11) (0.18) (12) (0.25) (13) (0.21) (14) (0.13)
572 (15) (0.08) (16) (0.04) (17) (0.05)
573 (18) (0.06) (19,24) (0) ..
574 INT-3 =DAY-SCHEDULE (1,24) (0) ..
575 INT-WEEK =WEEK-SCHEDULE (MON,FRI) INT-3 (SAT) INT-3 (SUN) INT-3
576 (HOL) INT-3 ..
577 INT-SHED = SCHEDULE THRU DEC 31 INT-WEEK
..
578
579
580
581 $ SYSTEM DESCRIPTION
582
583 ZAIR =ZONE-AIR OA-CFM/PER=
17
584 EXHAUST-CFM =
0
585 EXHAUST-EFF =
0.75
586 EXHAUST-STATIC = 0 ..
587
588
589 CONTROL = ZONE-CONTROL DESIGN-HEAT-T =
70
590 DESIGN-COOL-T =
75
591 HEAT-TEMP-SCH = HEAT-SCHED
592 COOL-TEMP-SCH = COOL-SCHED
593 THERMOSTAT-TYPE =
PROPORTIONAL
594 THROTTLING-RANGE = 0.1
..
595
596
597 SPACE1-1 =ZONE ZONE-AIR=ZAIR
598 SIZING-OPTION=ADJUST-LOADS
599 ZONE-CONTROL=CONTROL ..
600
601 SPACE2-1 =ZONE LIKE SPACE1-1 ..
602 SPACE3-1 =ZONE LIKE SPACE1-1 ..
603 SPACE4-1 =ZONE LIKE SPACE1-1 ..
604 SPACE5-1 =ZONE LIKE SPACE1-1 ..
605
606 ATTIC =ZONE ZONE-TYPE=UNCONDITIONED
..
607
608
609 S-AIR =SYSTEM-AIR MAX-OA-FRACTION =
1.0
610 OA-CONTROL = TEMP
..
611
612
613 S-CONT =SYSTEM-CONTROL COOLING-SCHEDULE=
COOLOFF
614 HEATING-SCHEDULE=
HEATOFF
615 PREHEAT-T =
44.6

```

```

616
MAX-SUPPLY-T=104
617
MIN-SUPPLY-T=55
..
618
S-FAN      =SYSTEM-FANS      FAN-SCHEDULE=FAN-SCHED
619
620
FAN-CONTROL=CONSTANT-VOLUME
621
MOTOR-PLACEMENT =
IN-AIRFLOW
622
FAN-PLACEMENT =
BLOW-THROUGH
623
SUPPLY-EFF=0.55575
624
MAX-FAN-RATIO =
1.1
625
MIN-FAN-RATIO =
0.3
626
NIGHT-CYCLE-CTRL=STAY-OFF
627
SUPPLY-DELTA-T =
1.815
628
SUPPLY-KW = 0.000531
..
629
630
631 $ COIL CURVE-FIT
632 HPACCoolCapFT = CURVE-FIT
633           TYPE = BI-QUADRATIC
634           COEFFICIENTS = (0.766956,0.0107756,-0.0000414703,0.00134961,
635           -0.000261144,0.000457488) ..
636 HPACCoolCapFFF = CURVE-FIT
637           TYPE = QUADRATIC
638           COEFFICIENTS = (0.8,0.2,0) ..
639 HPACCOOLEIRFT =
CURVE-FIT
640           TYPE = BI-QUADRATIC
641           COEFFICIENTS = (0.297145,0.0430933,-0.000748766,0.00597727,
642           0.000482112,-0.000956448) ..
643 HPACCOOLPLFFPLR =
CURVE-FIT
644           TYPE = QUADRATIC
645           COEFFICIENTS = (0.85,0.15,0) ..
646
647
648 S-EQUIP  =SYSTEM-EQUIPMENT  COOL-CAP-FT = SDL-C3
649
COOLING-EIR =
0.242745131
650
COOL-EIR-FT = SDL-C13
651
COOL-EIR-FPLR =
SDL-C18
652
COOL-SH-FT
=SDL-C23
653
COIL-BF-FT = HPACCoolCapFT
654
COIL-BF-FCFM = HPACCoolCapFFF
655
COIL-BF-FPLR =
HPACCOOLPLFFPLR
656
COIL-BF=0.19
657
COOL-FT-MIN=
70
658
HEAT-CAP-FT = SDL-C55
659
HEATING-EIR = 0.29751543
660
HEAT-EIR-FT = SDL-C60
661
HEAT-EIR-FPLR = SDL-C65
662
DEFROST-FRAC-FT = HPACCOOLEIRFT
663
OUTSIDE-FAN-T = 45
664
OUTSIDE-FAN-MODE = INTERMITTENT

```

```

665                                COMPRESSOR-TYPE =
666                                SINGLE-SPEED
667                                RATED-CCAP-FCFM = SDL-C78
668                                RATED-SH-FCFM=  SDL-C85
669                                RATED-CEIR-FCFM= SDL-C93
670                                RATED-HCAP-FCFM= SDL-C100
671                                CRANKCASE-HEAT= 0.05
672                                CRANKCASE-MAX-T= 39.92
673                                ..
674
675
676 S-TERM          =SYSTEM-TERMINAL REHEAT-DELTA-T=
677 50
678                                MIN-CFM-RATIO= 1.0  ..
679
680 SYST-1          =SYSTEM          SYSTEM-TYPE=
681 PSZ
682                                SYSTEM-CONTROL= S-CONT
683                                SYSTEM-FANS= S-FAN
684                                SYSTEM-TERMINAL= S-TERM
685                                SYSTEM-EQUIPMENT=
686                                S-EQUIP
687                                HEAT-SOURCE=
688                                HEAT-PUMP
689
690                                PREHEAT-SOURCE=
691                                HEAT-PUMP
692                                ECONO-LIMIT-T=
693                                82.4
694                                ECONO-LOW-LIMIT=
695                                32
696                                RETURN-AIR-PATH= DIRECT
697                                SIZING-OPTION =
698                                NON-COINCIDENT
699
700                                ZONE-NAMES= (SPACE5-1,SPACE1-1,SPACE2-1
701
702                                SPACE3-1,SPACE4-1,ATTIC)
703                                ..
704
705 HP-1            = PLANT-ASSIGNMENT SYSTEM-NAMES = (SYST-1)
706                                HP-LOOP-HEATING = FROM-SYSTEMS
707                                HP-LOOP-COOLING = FROM-SYSTEMS
708                                DHW-SIZE          = 40
709                                DHW-GAL/MIN      =
710                                0.0486
711                                DHW-SCH          = DHW-SCHED
712                                DHW-INLET-T-SCH = DHWINLETSCH-1
713                                DHW-SUPPLY-T     =
714                                131
715                                DHW-TYPE         = ELECTRIC
716                                DHW-EIR          = 1
717                                DHW-EIR-FT       = DHWHPEIRFT
718                                DHW-HEAT-RATE-FT = DHWHPCAPFT
719                                DHW-EIR-FPLR     = DHWGEIRFPLR
720                                DHW-PUMP-ELEC   = 0
721                                MAX-FLUID-T     = 140
722                                MIN-FLUID-T     = 50
723                                FLUID-VOLUME    = 15
724                                ..
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743 $===== HOURLY-REPORT FOR SYSTEM
744 =====
745
746 $ HOURLY-REPORT FOR SYSTEM PART
747 HRSCH-2          = SCHEDULE
748 THRU DEC 31 (ALL) (1,24) (1) ..

```

```

718
719 S1_ZT      = REPORT-BLOCK
720           VARIABLE-TYPE=SPACE1-1
721           VARIABLE-LIST=(6,14)
           ..

722
723 S2_ZT      = REPORT-BLOCK
724           VARIABLE-TYPE=SPACE2-1
725           VARIABLE-LIST=(6,14)
           ..

726
727 S3_ZT      = REPORT-BLOCK
728           VARIABLE-TYPE=SPACE3-1
729           VARIABLE-LIST=(6,14) ..
730
731 S4_ZT      = REPORT-BLOCK
732           VARIABLE-TYPE=SPACE4-1
733           VARIABLE-LIST=(6,14) ..
734
735 S5_ZT      = REPORT-BLOCK
736           VARIABLE-TYPE=SPACE5-1
737           VARIABLE-LIST=(6,14)
           ..

738
739 SYS1      = REPORT-BLOCK
740           VARIABLE-TYPE=SYST-1
741           VARIABLE-LIST=(1,2) ..
742
743 PPRT1     = HOURLY-REPORT
744           REPORT-SCHEDULE = HRSCH-2
745           REPORT-BLOCK = (S1_ZT,S2_ZT,S3_ZT,S4_ZT,S5_ZT,SYST1) ..
746
747 $=====
748
749
750
751 END ..
752 COMPUTE SYSTEMS ..
753
754
755 INPUT PLANT ..
756
757           PLANT-REPORT SUMMARY=(ALL-SUMMARY)
758           REPORT-FREQUENCY = HOURLY
759           HOURLY-DATA-SAVE = FORMATTED ..
760
761 $===== HOURLY-REPORT FOR PLANT
762 =====
763
764 HRSCH-3    = SCHEDULE
765           THRU DEC 31 (ALL) (1,24) (1) ..
766
767
768 ENDU      = REPORT-BLOCK
769           VARIABLE-TYPE=END-USE
770           VARIABLE-LIST=(1,3,5,6,9)
           ..

771
772 PPRT1     = HOURLY-REPORT
773           REPORT-SCHEDULE = HRSCH-3
774           REPORT-BLOCK = (ENDU) ..
775
776 $=====
777
778
779 END ..
780 COMPUTE PLANT ..
781
782
783
784 STOP ..

```

2.3.2 Reference Model 2: Five-Zone Model in Chicago, IL (PVAV System)

In this section the DOE-2 input file for "Case 2: Five-Zone Model in Chicago, IL" is described.

```

1  $===== SIMULATION ZONING =====
2
3  INPUT LOADS ..
4
5  TITLE          LINE-1 *SAMPLE PROVIDED BY PROF.JEFF HABERL*
6                LINE-2 *CHICAGO, TX, CLIMATE ZONE 5A*
7                LINE-3 *ASHRAE 90.1-2016 REQUIREMENTS SATISFIED*
8                LINE-4 *STUDY FOR BUILDING OCCUPANCY PROFILE ANALYSIS* ..
9
10             RUN-PERIOD      JAN 1 2019 THRU DEC 31 2019  ..
11
12             ABORT           ERRORS ..
13             DIAGNOSTIC     WARNINGS ..
14             LOADS-REPORT   SUMMARY = (ALL-SUMMARY)
15                                 REPORT-FREQUENCY = HOURLY
16                                 HOURLY-DATA-SAVE = FORMATTED
17                                 VERIFICATION = (ALL-VERIFICATION) ..
18
19             BUILDING-LOCATION LATITUDE=41.98
20                                 LONGITUDE=87.92
21                                 GROUND-T = (67.838, 67.604, 67.604, 67.838,
22                                 68.18,72.05,73.184, 73.526, 73.634, 69.944,
23                                 68.954, 68.342)
24                                 DAYLIGHT-SAVINGS = NO
25                                 ALTITUDE=659.45
26                                 TIME-ZONE=6
27                                 AZIMUTH=0.0  ..
28
29
30
31  $ BUILDING DESCRIPTION
32
33  $===== BUILDING CONSTRUCTION =====
34
35
36  $ CONSTRUCTION AND GLASS-TYPES
37
38  $ MATERIAL PROPERTY (IP UNITS)
39  $ ALL VALUES CONVERTED FROM SI UNITS IN PNNL SMALL OFFICE MODEL FOR 90.1-2016
40  $ ROOF AND CEILING PROPERTY
41  ROOF_BUIL      = MAT              THICKNESS = 0.03116798
42                                 CONDUCTIVITY = 0.092446272
43                                 DENSITY = 69.9193264
44                                 SPECIFIC-HEAT = 0.348715014  ..
45
46  ROOF_INS_2     = MAT              RESISTANCE = 45.98476874  ..
47
48  ROOF_SUR_1     = MAT              THICKNESS = 0.002624672
49                                 CONDUCTIVITY = 26.16229498
50                                 DENSITY = 488.4364373
51                                 SPECIFIC-HEAT = 0.11942295  ..
52
53  ROOF_ASPHT     = MAT              THICKNESS = 0.010498688
54                                 CONDUCTIVITY = 0.023111568
55                                 DENSITY = 69.9193264
56                                 SPECIFIC-HEAT = 0.300945834  ..
57
58  ROOF_WOOD      = MAT              THICKNESS = 0.052165356
59                                 CONDUCTIVITY = 0.069334704
60                                 DENSITY = 33.96081568
61                                 SPECIFIC-HEAT = 0.289003539  ..
62
63
64  $ SLAB PROPERTY
65  SLAB_CONC200   = MAT              THICKNESS = 0.666666688
66                                 CONDUCTIVITY = 1.334693052
67                                 DENSITY = 144.9577463
68                                 SPECIFIC-HEAT = 0.198719789  ..
69
70  SLAB_CONC100   = MAT              THICKNESS = 0.333333344
71                                 CONDUCTIVITY = 1.334693052
72                                 DENSITY = 144.9577463
73                                 SPECIFIC-HEAT = 0.198719789  ..

```

```

74
75 SLAB_CARP      = MAT      RESISTANCE = 1.22923033 ..
76
77
78 $ WALL PROPERTY
79 WALL_STU      = MAT      THICKNESS = 0.083333336
80 CONDUCTIVITY = 0.416008224
81 DENSITY      = 115.8663123
82 SPECIFIC-HEAT = 0.200630556 ..
83
84 WALL_GYP1     = MAT      THICKNESS = 0.052165356
85 CONDUCTIVITY = 0.092446272
86 DENSITY      = 49.942376
87 SPECIFIC-HEAT = 0.260342031 ..
88
89 WALL_GYP2     = MAT      THICKNESS = 0.041666668
90 CONDUCTIVITY = 0.092446272
91 DENSITY      = 49.942376
92 SPECIFIC-HEAT = 0.260342031 ..
93
94 WALL_INS_2    = MAT      RESISTANCE = 17.42897129 ..
95
96
97 $ WINDOW PROPERTY
98 WIN_GLS3     = GLASS-TYPE GLASS-CONDUCTANCE = 0.3954
99 VIS-TRANS    = 0.452
100 SHADING-COEF =
0.41954023
101 PANES = 2 ..
102
103 DOOR1        = GLASS-TYPE GLASS-CONDUCTANCE = 0.370
104 SHADING-COEF = 0.7 ..
105
106 AIR-LAYER    = CONSTRUCTION U = 1.11 ..
107
108
109 $ MATERIAL LAYERS
110 ATTIC-R1     =LAYERS =MAT=(AR02,PW04) ..
111 ATTIC-R2     =LAYERS =MAT=(PW04) ..
112 ROOF_1       =LAYERS =MAT=(ROOF_INS_2,GP02) ..
113 EX_SLAB_1    =LAYERS =MAT=(SLAB_CONC200,CP02) ..
114 EX_WALL_1    =LAYERS =MAT=(SC01,GP02,WALL_INS_2,GP02) ..
115 IN_WALL_1    =LAYERS =MAT=(GP01,GP01) ..
116 IN_SLAB_1    =LAYERS =MAT=(SLAB_CONC100,CP02) ..
117 CEIL_MAT1    =LAYERS =MAT=(AC02,GP01) ..
118
119
120 $ MATERIAL CONSTRUCTION
121 EXT_SLAB     =CONSTRUCTION LAYERS = EX_SLAB_1
122 ABSORPTANCE = 0.7 ..
123 NONRES_EXT_WALL =CONSTRUCTION LAYERS = EX_WALL_1
124 ABSORPTANCE = 0.7 ..
125 INT_WALL     =CONSTRUCTION LAYERS = IN_WALL_1
126 ABSORPTANCE = 0.7 ..
127 CEIL_MAT2    =CONSTRUCTION LAYERS = ROOF_1
128 ABSORPTANCE = 0.7 ..
129 ATTIC-ROOF   =CONSTRUCTION LAYERS = ATTIC-R1
130 ABSORPTANCE = 0.7 ..
131 ATTIC-SOFFIT =CONSTRUCTION LAYERS = ATTIC-R2
132 ABSORPTANCE = 0.7 ..
133 DOOR2        =CONSTRUCTION U = 1.426492621
134 ABSORPTANCE = 0.7 ..
135
136 $ OCCUPANCY SCHEDULE
137 OC-1         =DAY-SCHEDULE (1,6) (0.0)
138 (7) (0.11)
139 (8) (0.21)
140 (9,12) (1.0)
141 (13) (0.53)
142 (14,17) (1.0)
143 (18) (0.32)
144 (19,22) (0.11)
145 (23) (0.05)

```

```

146 (24) (0.0) ..
147
148 OC-2 =DAY-SCHEDULE (1,6) (0.0)
149 (7,8) (0.1)
150 (9,12) (0.3)
151 (13,17) (0.1)
152 (18,19) (0.05)
153 (20,24) (0.0) ..
154
155 OC-3 =DAY-SCHEDULE (1,6) (0.0)
156 (7,18) (0.05)
157 (19,24) (0.0) ..
158
159 OC-4 =DAY-SCHEDULE (1,24) (0.0) ..
160 OC-5 =DAY-SCHEDULE (1,24) (1.0) ..
161
162
163 OC-WEEK =WEEK-SCHEDULE (WD) OC-1 (SAT) OC-4 (SUN) OC-4 (HOL) OC-4 ..
164 OC-WEEK2 =WEEK-SCHEDULE (WD) OC-4 (SAT) OC-4 (SUN) OC-4 (HOL) OC-4 ..
165 OC-WEEK3 =WEEK-SCHEDULE (WD) OC-5 (SAT) OC-5 (SUN) OC-5 (HOL) OC-5 ..
166
167 OCCUPY-1 =SCHEDULE THRU DEC 31 OC-WEEK ..
168 OCCUPY-2 =SCHEDULE THRU DEC 31 OC-WEEK2 ..
169 OCCUPY-3 =SCHEDULE THRU DEC 31 OC-WEEK3 ..
170
171
172
173 $ LIGHTING SCHEDULE
174
175 LT-1 =DAY-SCHEDULE (1,5) (0.18)
176 (6,7) (0.23)
177 (8) (0.42)
178 (9,12) (0.9)
179 (13) (0.8)
180 (14,17) (0.9)
181 (18) (0.61)
182 (19,20) (0.42)
183 (21,22) (0.32)
184 (23) (0.23)
185 (24) (0.18) ..
186
187 LT-0 =DAY-SCHEDULE (1,6) (0.0)
188 (7) (0.11)
189 (8) (0.21)
190 (9,12) (1.0)
191 (13) (0.53)
192 (14,17) (1.0)
193 (18) (0.32)
194 (19,22) (0.11)
195 (23) (0.05)
196 (24) (0.0) ..
197
198 LT-2 =DAY-SCHEDULE (1,6) (0.05)
199 (7,8) (0.1)
200 (9,12) (0.3)
201 (13,17) (0.15)
202 (18,24) (0.05) ..
203
204 LT-3 =DAY-SCHEDULE (1,24) (0.18) ..
205 LT-4 =DAY-SCHEDULE (1,24) (0.0) ..
206 LT-5 =DAY-SCHEDULE (1,24) (1.0) ..
207
208
209 LT-WEEK =WEEK-SCHEDULE (WD) LT-1 (SAT) LT-3 (SUN) LT-3 (HOL) LT-3 ..
210 LT-WEEK2 =WEEK-SCHEDULE (WD) LT-3 (SAT) LT-3 (SUN) LT-3 (HOL) LT-3 ..
211 LT-WEEK3 =WEEK-SCHEDULE (WD) LT-5 (SAT) LT-5 (SUN) LT-5 (HOL) LT-5 ..
212
213
214 LIGHTS-1 =SCHEDULE THRU DEC 31 LT-WEEK ..
215 LIGHTS-2 =SCHEDULE THRU DEC 31 LT-WEEK2 ..
216 LIGHTS-3 =SCHEDULE THRU DEC 31 LT-WEEK3
217 ..

```

```

218
219 $ OFFICE EQUIPMENT SCHEDULE
220 EQ-1      =DAY-SCHEDULE      (1,5) (0.5)
221          (6,12) (1.0)
222          (13) (0.94)
223          (14,17) (1.0)
224          (18) (0.5)
225          (19,24) (0.2) ..
226
227 EQ-0      =DAY-SCHEDULE      (1,6) (0.0)
228          (7) (0.11)
229          (8) (0.21)
230          (9,12) (1.0)
231          (13) (0.53)
232          (14,17) (1.0)
233          (18) (0.32)
234          (19,22) (0.11)
235          (23) (0.05)
236          (24) (0.0) ..
237
238 EQ-2      =DAY-SCHEDULE      (1,6) (0.3)
239          (7,8) (0.4)
240          (9,12) (0.5)
241          (13,17) (0.35)
242          (18,24) (0.3) ..
243
244 EQ-3      =DAY-SCHEDULE      (1,24) (0.2) ..
245 EQ-4      =DAY-SCHEDULE      (1,24) (0.0) ..
246 EQ-5      =DAY-SCHEDULE      (1,24) (1.0) ..
247
248
249 EQ-WEEK    =WEEK-SCHEDULE      (WD) EQ-1 (SAT) EQ-3 (SUN) EQ-3 (HOL) EQ-3 ..
250 EQ-WEEK2   =WEEK-SCHEDULE      (WD) EQ-3 (SAT) EQ-3 (SUN) EQ-3 (HOL) EQ-3 ..
251 EQ-WEEK3   =WEEK-SCHEDULE      (WD) EQ-5 (SAT) EQ-5 (SUN) EQ-5 (HOL) EQ-5 ..
252
253 EQUIP-1    =SCHEDULE           THRU DEC 31 EQ-WEEK ..
254 EQUIP-2    =SCHEDULE           THRU DEC 31 EQ-WEEK2 ..
255 EQUIP-3    =SCHEDULE           THRU DEC 31 EQ-WEEK3 ..
256
257
258 $ INFILTRATION SCHEDULE
259 IF-1      =DAY-SCHEDULE      (1,6) (1.0)
260          (7,19) (0.25)
261          (20,24) (1.0) ..
262
263 IF-2      =DAY-SCHEDULE      (1,7) (1.0)
264          (8,18) (0.25)
265          (19,24) (1.0) ..
266
267 IF-3      =DAY-SCHEDULE      (1,24) (0.0) ..
268 IF-4      =DAY-SCHEDULE      (1,24) (1.0) ..
269 IF-5      =DAY-SCHEDULE      (1,24) (0.25) ..
270
271
272 IF-WEEK    =WEEK-SCHEDULE      (WD) IF-1 (SAT) IF-2 (SUN) IF-4 (HOL) IF-4 ..
273 IF-WEEK2   =WEEK-SCHEDULE      (WD) IF-4 (SAT) IF-4 (SUN) IF-4 (HOL) IF-4 ..
274 IF-WEEK3   =WEEK-SCHEDULE      (WD) IF-5 (SAT) IF-5 (SUN) IF-5 (HOL) IF-5 ..
275
276 INFIL-SCH  =SCHEDULE           THRU DEC 31 IF-WEEK ..
277 INFIL-SCH2 =SCHEDULE           THRU DEC 31 IF-WEEK2 ..
278 INFIL-SCH3 =SCHEDULE           THRU DEC 31 IF-WEEK3 ..
279
280
281
282 $===== SPACE DEFAULTS & DESCRIPTION =====
283
284
285 $ SET DEFAULT VALUE
286
287 SET-DEFAULT FOR SPACE FLOOR-WEIGHT = 0 ..
288 SET-DEFAULT FOR WINDOW HEIGHT=5.0
289                               GLASS-TYPE=WIN_GLS3 Y=1 ..
290 SET-DEFAULT FOR EXTERIOR-WALL CONSTRUCTION=NONRES_EXT_WALL ..

```



```

291
292
293 $ GENERAL SPACE DEFINITION
294
295 OFFICE      =SPACE-CONDITIONS  PEOPLE-SCHEDULE      =OCCUPY-1
296                                     NUMBER-OF-PEOPLE      =31
297                                     PEOPLE-HEAT-GAIN       =450
298                                     LIGHTING-SCHEDULE     =LIGHTS-1
299                                     LIGHTING-W/SQFT       = 0.79
300                                     EQUIP-SCHEDULE        = EQUIP-1
301                                     EQUIPMENT-W/SQFT     = 0.63
302                                     INF-METHOD          = AIR-CHANGE
303                                     AIR-CHANGES/HR      = 0.0
304                                     INF-SCHEDULE         =INFIL-SCH  ..
305
306
307 $ SPECIFIC SPACE DETAILS
308
309 $ ATTIC
310 ATTIC-SC    = SPACE-CONDITIONS
311             ZONE-TYPE = UNCONDITIONED
312             FLOOR-WEIGHT = 0 ..           $ CUSTOM WEITING FACTOR
313
314 ATTIC      = SPACE      S-C = ATTIC-SC  AREA = 6113.686  VOLUME = 24533.31
315             X = 0      Y = 0      Z = 0      AZ = 0 ..
316 N-ROOF = POLYGON
317         (92.81,62.53) (-1.97,62.53) (30.28,32.03) (60.56,32.03) ..
318 S-ROOF = POLYGON
319         (-1.97,-1.97) (92.81,-1.97) (60.56,32.03) (30.28,32.03) ..
320 E-GABLE = POLYGON
321         (0,0) (64.5,0) (32.25,34) ..
322 W-GABLE = POLYGON
323         (-1.97,62.53,10) (-1.97,-1.97,10) (30.28,30.28,20.77) ..
324
325
326
327 $ ROOF RAISED
328 N-ROOF-EXT = ROOF      CONSTRUCTION = ATTIC-ROOF
329                                     POLYGON = S-ROOF
330                                     TILT =18.5, AZ = 0,
331                                     X= 90.84 Y = 60.56 Z = 10.0 ..
332
333 S-ROOF-EXT = ROOF      CONSTRUCTION = ATTIC-ROOF
334                                     POLYGON = S-ROOF
335                                     TILT =18.5, AZ = 180, Z = 10.0 ..
336
337 E-GABLE-EXT = ROOF     CONSTRUCTION = ATTIC-ROOF
338                                     POLYGON = E-GABLE
339                                     TILT =18.2, AZ = 90
340                                     X = 92.81 Y = -1.97 Z = 10.0 ..
341
342 W-GABLE-EXT = ROOF     CONSTRUCTION = ATTIC-ROOF
343                                     POLYGON = E-GABLE
344                                     TILT =18.2, AZ = 270
345                                     X = -1.97 Y = 62.53 Z = 10.0 ..
346
347
348 N-ROOF-SOFFIT = BUILDING-SHADE  HEIGHT = 1.97  WIDTH = 94.78
349                                     X=-1.97  Y=60.6  Z=10
350                                     TRANSMITTANCE = 0.0
351                                     AZIMUTH = 180  TILT = 180 ..
352 S-ROOF-SOFFIT = BUILDING-SHADE  HEIGHT = 1.97  WIDTH =
353 94.78
354                                     X=-1.97  Y=0  Z=10
355                                     TRANSMITTANCE = 0.0
356                                     AZIMUTH = 180  TILT = 180 ..
357 E-ROOF-SOFFIT = BUILDING-SHADE  HEIGHT = 1.97  WIDTH =
358 60.56
359                                     X=90.85  Y=0  Z=10
360                                     TRANSMITTANCE = 0.0
361                                     AZIMUTH = 90  TILT = 180 ..
362 W-ROOF-SOFFIT = BUILDING-SHADE  HEIGHT = 1.97  WIDTH =
363 60.56

```

```

361                                     X=0 Y=0 Z=10
362                                     TRANSMITTANCE = 0.0
363                                     AZIMUTH = 90 TILT = 180 ..
364
365
366
367 SPACE1-1      =SPACE                SPACE-CONDITIONS = OFFICE
368                                     AREA = 1221.28925 VOLUME = 12221.4264
369                                     NUMBER-OF-PEOPLE = 7 ..
370         FRONT-1  =EXTERIOR-WALL      HEIGHT = 10 WIDTH = 90.8
371                                     X=0 Y=0 Z=0 AZIMUTH = 180 ..
372
373         WF-1      =WINDOW              WIDTH = 6 X = 4.56 Y = 2.95 ..
374         WF-2      =WINDOW              WIDTH = 6 X = 19.72 Y = 2.95 ..
375         WF-3      =WINDOW              WIDTH = 6 X = 34.84 Y = 2.95 ..
376         WF-4      =WINDOW              WIDTH = 6 X = 50.00 Y = 2.95 ..
377         WF-5      =WINDOW              WIDTH = 6 X = 65.12 Y = 2.95 ..
378         WF-6      =WINDOW              WIDTH = 6 X = 80.28 Y = 2.95 ..
379         DF-1      =WINDOW              WIDTH = 6 HEIGHT = 7
380                                     X = 42.42 Y = 0
381                                     GLASS-TYPE=WIN_GLS3 ..
382
383         C1-1      =INTERIOR-WALL      AREA = 1221.28925 NEXT-TO ATTIC
384                                     CONSTRUCTION = CEIL_MAT2 ..
385
386         F1-1      =UNDERGROUND-FLOOR  AREA = 1221.28925
387                                     CONSTRUCTION = EXT_SLAB ..
388
389         SB12      =INTERIOR-WALL      AREA=231.931 NEXT-TO SPACE2-1
390                                     CONSTRUCTION = INT_WALL ..
391
392         SB14      =INTERIOR-WALL      LIKE SB12 NEXT-TO SPACE4-1 ..
393         SB15      =INTERIOR-WALL      AREA 580 NEXT-TO SPACE5-1
394                                     CONSTRUCTION = INT_WALL ..
395
396 SPACE2-1      =SPACE                SPACE-CONDITIONS = OFFICE
397                                     AREA = 724.4845 VOLUME = 7249.7832
398                                     NUMBER-OF-PEOPLE = 4 ..
399
400         RIGHT-1  =EXTERIOR-WALL      HEIGHT = 10 WIDTH = 60.5
401                                     X=90.8 Y=0 Z=0 AZIMUTH = 90 ..
402
403         WR-1      =WINDOW              WIDTH = 6 X = 4.56 Y = 2.95 ..
404         WR-2      =WINDOW              WIDTH = 6 X = 19.72 Y = 2.95 ..
405         WR-3      =WINDOW              WIDTH = 6 X = 34.84 Y = 2.95 ..
406         WR-4      =WINDOW              WIDTH = 6 X = 50.00 Y = 2.95 ..
407
408         C2-1      =INTERIOR-WALL      AREA = 724.4845 NEXT-TO ATTIC
409                                     CONSTRUCTION = CEIL_MAT2 ..
410
411         F2-1      =UNDERGROUND-FLOOR  AREA = 724.4845
412                                     CONSTRUCTION = EXT_SLAB ..
413
414         SB23      =INTERIOR-WALL      AREA = 231.931 NEXT-TO SPACE3-1
415                                     CONSTRUCTION = INT_WALL ..
416
417         SB25      =INTERIOR-WALL      AREA = 277 NEXT-TO SPACE5-1
418                                     CONSTRUCTION = INT_WALL ..
419
420 SPACE3-1      =SPACE                SPACE-CONDITIONS = OFFICE
421                                     AREA = 1221.28925 VOLUME = 12221.4264
422                                     NUMBER-OF-PEOPLE = 7 ..
423
424         BACK-1   =EXTERIOR-WALL      HEIGHT = 10 WIDTH = 90.8
425                                     X=90.8 Y=60.5 Z=0 AZIMUTH = 0 ..
426
427         WB-1      =WINDOW              WIDTH = 6 X = 4.56 Y = 2.95 ..
428         WB-2      =WINDOW              WIDTH = 6 X = 19.72 Y = 2.95 ..
429         WB-3      =WINDOW              WIDTH = 6 X = 34.84 Y = 2.95 ..
430         WB-4      =WINDOW              WIDTH = 6 X = 50.00 Y = 2.95 ..
431         WB-5      =WINDOW              WIDTH = 6 X = 65.12 Y = 2.95 ..
432         WB-6      =WINDOW              WIDTH = 6 X = 80.28 Y = 2.95 ..
433         DB-1      =DOOR                WIDTH = 3 HEIGHT = 7

```

```

434          X = 28.08  Y = 0
435          CONSTRUCTION = DOOR2  ..
436      DB-2  =DOOR          WIDTH = 3  HEIGHT = 7
437          X = 41.92  Y = 0
438          CONSTRUCTION = DOOR2  ..
439
440      C3-1  =INTERIOR-WALL  AREA = 1221.28925  NEXT-TO ATTIC
441          CONSTRUCTION = CEIL_MAT2  ..
442
443      F3-1  =UNDERGROUND-FLOOR  AREA = 1221.28925
444          CONSTRUCTION = EXT_SLAB  ..
445
446      SB34  =INTERIOR-WALL  AREA = 231.931  NEXT-TO SPACE4-1
447          CONSTRUCTION = INT_WALL  ..
448
449      SB35  =INTERIOR-WALL  AREA = 580  NEXT-TO SPACE5-1
450          CONSTRUCTION = INT_WALL  ..
451
452  SPACE4-1  =SPACE          SPACE-CONDITIONS = OFFICE
453          AREA = 724.4845  VOLUME = 7249.7832
454          NUMBER-OF-PEOPLE = 4  ..
455
456      LEFT-1  =EXTERIOR-WALL  HEIGHT = 10  WIDTH = 60.5
457          X=0  Y=60.5  Z=0  AZIMUTH = 270  ..
458
459      WL-1  =WINDOW          WIDTH = 6  X = 4.56  Y = 2.95  ..
460      WL-2  =WINDOW          WIDTH = 6  X = 19.72  Y = 2.95  ..
461      WL-3  =WINDOW          WIDTH = 6  X = 34.84  Y = 2.95  ..
462      WL-4  =WINDOW          WIDTH = 6  X = 50.00  Y = 2.95  ..
463
464      C4-1  =INTERIOR-WALL  AREA = 724.4845  NEXT-TO ATTIC
465          CONSTRUCTION = CEIL_MAT2  ..
466
467      F4-1  =UNDERGROUND-FLOOR  AREA = 724.4845
468          CONSTRUCTION = EXT_SLAB  ..
469
470      SB45  =INTERIOR-WALL  AREA = 277  NEXT-TO SPACE5-1
471          CONSTRUCTION = INT_WALL  ..
472
473  SPACE5-1  =SPACE          SPACE-CONDITIONS = OFFICE
474          AREA = 1611.0899  VOLUME = 16122.1672
475          NUMBER-OF-PEOPLE = 9  ..
476
477      C5-1  =INTERIOR-WALL  AREA = 1611.0899  NEXT-TO ATTIC
478          CONSTRUCTION = CEIL_MAT2  ..
479
480      F5-1  =UNDERGROUND-FLOOR  AREA = 1611.0899
481          CONSTRUCTION = EXT_SLAB  ..
482
483  END  ..
484  COMPUTE  LOADS  ..
485
486
487
488  $----- SYSTEM DESCRIPTION -----
489
490  INPUT SYSTEMS  ..
491
492          SYSTEMS-REPORT  SUMMARY=(ALL-SUMMARY)
493          REPORT-FREQUENCY = HOURLY
494          HOURLY-DATA-SAVE = FORMATTED  ..
495
496
497  $ SYSTEMS SCHEDULES
498
499  FAN-1      =DAY-SCHEDULE  (1,6) (0) (7,19) (1) (20,24) (0)  ..
500  FAN-2      =DAY-SCHEDULE  (1,24) (0)  ..
501  FAN-3      =DAY-SCHEDULE  (1,24) (1)  ..
502  FAN-4      =DAY-SCHEDULE  (1,6) (0) (7,23) (1) (24) (0)  ..
503  FAN-5      =DAY-SCHEDULE  (1,8) (0) (9,17) (1) (18,24) (0)  ..
504
505  FAN-WEEK   =WEEK-SCHEDULE  (WD) FAN-1 (WEH) FAN-2  ..
506  FAN-WEEK2  =WEEK-SCHEDULE  (WD) FAN-2 (WEH) FAN-2  ..

```

```

507 FAN-WEEK3      =WEEK-SCHEDULE      (WD) FAN-3 (WEH) FAN-3 ..
508
509 FAN-SCHED      =SCHEDULE              THRU DEC 31 FAN-WEEK ..
510 FAN-SCHED2     =SCHEDULE              THRU DEC 31 FAN-WEEK2 ..
511 FAN-SCHED3     =SCHEDULE              THRU DEC 31 FAN-WEEK3 ..
512
513
514 $ THERMOSTAT SET-POINTS FOR HEATING AND COOLING
515 $ SET TEMPERATURES CONVERTED TO IP UNITS FROM SI UNITS
516
517 HEAT-1         =DAY-SCHEDULE      (1,6) (60.01) (7) (69.98)
518                                     (8,19) (69.98) (20,24) (60.01) ..
519 HEAT-2         =DAY-SCHEDULE      (1,5) (60.01) (6) (64.04) (7) (68.0)
520                                     (8,17) (69.98) (18,24) (60.01) ..
521 HEAT-3         =DAY-SCHEDULE      (1,24) (60.01) ..
522 HEAT-4         =DAY-SCHEDULE      (1,24) (69.98) ..
523
524 HEAT-WEEK      =WEEK-SCHEDULE      (MON,FRI) HEAT-1 (SAT) HEAT-3 (SUN) HEAT-3
525                                     (HOL) HEAT-3 ..
526 HEAT-WEEK2     =WEEK-SCHEDULE      (MON,FRI) HEAT-3 (SAT) HEAT-3 (SUN)
HEAT-3
527                                     (HOL) HEAT-3 ..
528 HEAT-WEEK3     =WEEK-SCHEDULE      (MON,FRI) HEAT-4 (SAT) HEAT-4 (SUN)
HEAT-4
529                                     (HOL) HEAT-4 ..
530
531 HEAT-SCHED     =SCHEDULE              THRU DEC 31 HEAT-WEEK ..
532 HEAT-SCHED2    =SCHEDULE              THRU DEC 31 HEAT-WEEK2 ..
533 HEAT-SCHED3    =SCHEDULE              THRU DEC 31 HEAT-WEEK3 ..
534
535
536 COOLOFF        =SCHEDULE              THRU DEC 31 (ALL) (1,24) (1) ..
537 HEATOFF        =SCHEDULE              THRU DEC 31 (ALL) (1,24) (1) ..
538
539
540 COOL-1         =DAY-SCHEDULE      (1,6) (84.99) (7)
541                                     (8,18) (75.00) (19,24) (84.99) ..
542 COOL-2         =DAY-SCHEDULE      (1,5) (84.99) (6) (78.08) (7) (77.0)
543                                     (8,17) (75.00) (18,24) (84.99) ..
544 COOL-3         =DAY-SCHEDULE      (1,24) (84.99) ..
545 COOL-4         =DAY-SCHEDULE      (1,24) (75.00) ..
546
547 COOL-WEEK      =WEEK-SCHEDULE      (MON,FRI) COOL-1 (SAT) COOL-3 (SUN) COOL-3
548                                     (HOL) COOL-3 ..
549 COOL-WEEK2     =WEEK-SCHEDULE      (MON,FRI) COOL-3 (SAT) COOL-3 (SUN)
COOL-3
550                                     (HOL) COOL-3 ..
551 COOL-WEEK3     =WEEK-SCHEDULE      (MON,FRI) COOL-4 (SAT) COOL-4 (SUN)
COOL-4
552                                     (HOL) COOL-4 ..
553
554
555 COOL-SCHED     =SCHEDULE              THRU DEC 31 COOL-WEEK
..
556 COOL-SCHED2    =SCHEDULE              THRU DEC 31 COOL-WEEK2
..
557 COOL-SCHED3    =SCHEDULE              THRU DEC 31 COOL-WEEK3
..
558
559
560 HVAC-HEAT      =SCHEDULE              THRU DEC 31 (ALL) (1,24) (1) ..
561 HVAC-COOL      =SCHEDULE              THRU DEC 31 (ALL) (1,24) (1)
..
562
563 24HR-OFF       =SCHEDULE              THRU DEC 31 (ALL) (1,24) (0)
..
564
565 DHW-SCHED      =SCHEDULE              THRU DEC 31 (ALL) (1,24) (1)
..
566 DHWINLETSCH-1 =SCHEDULE              THRU DEC 31 (ALL) (1,24) (140)
..
567

```

```

568 INT-1      =DAY-SCHEDULE  (1,7) (0) (8) (0.35) (9) (0.69) (10)
      (0.43)
569          (11) (0.37) (12) (0.43) (13) (0.58) (14) (0.48)
570          (15,16) (0.37) (17) (0.46) (18) (0.62)
571          (19) (0.12) (20,21) (0.04) (22,24) (0)
      ..
572 INT-2      =DAY-SCHEDULE  (1,7) (0) (8) (0.16) (9) (0.14) (10) (0.21)
573          (11) (0.18) (12) (0.25) (13) (0.21) (14) (0.13)
574          (15) (0.08) (16) (0.04) (17) (0.05)
575          (18) (0.06) (19,24) (0) ..
576 INT-3      =DAY-SCHEDULE  (1,24) (0) ..
577 INT-WEEK   =WEEK-SCHEDULE (MON,FRI) INT-3 (SAT) INT-3 (SUN) INT-3
578          (HOL) INT-3 ..
579 INT-SHED   = SCHEDULE     THRU DEC 31 INT-WEEK
      ..
580
581
582
583 $ SYSTEM DESCRIPTION
584
585 ZAIR        =ZONE-AIR      OA-CFM/PER= 17
586          EXHAUST-CFM =
          0
587          EXHAUST-EFF =
          0.75
588          EXHAUST-STATIC = 0
          ..
589
590
591 CONTROL    = ZONE-CONTROL  DESIGN-HEAT-T = 70
592          DESIGN-COOL-T = 75
593          HEAT-TEMP-SCH = HEAT-SCHED
594          COOL-TEMP-SCH = COOL-SCHED
595          THERMOSTAT-TYPE = PROPORTIONAL
596          THROTTLING-RANGE = 0.1
          ..
597
598 SPACE1-1   =ZONE          ZONE-AIR=ZAIR
599
          SIZING-OPTION=ADJUST-LOADS
600
          ZONE-CONTROL=CONTROL ..
601
602 SPACE2-1   =ZONE          LIKE SPACE1-1 ..
603 SPACE3-1   =ZONE          LIKE SPACE1-1 ..
604 SPACE4-1   =ZONE          LIKE SPACE1-1 ..
605 SPACE5-1   =ZONE          LIKE SPACE1-1 ..
606
607 ATTIC      =ZONE          ZONE-TYPE=UNCONDITIONED
608 ..
609
610
611 S-CONT     =SYSTEM-CONTROL COOLING-SCHEDULE=
      COOLOFF
612          HEATING-SCHEDULE=
          HEATOFF
613          COOL-CONTROL =
          CONSTANT
614          PREHEAT-T =
          44.6
615
          MAX-SUPPLY-T=104
616
          MIN-SUPPLY-T=55
          ..
617
618
619 S-AIR      =SYSTEM-AIR     MAX-OA-FRACTION =
      1.0
620          OA-CONTROL = TEMP

```

```

621
622
623 S-FAN      =SYSTEM-FANS      FAN-SCHEDULE=FAN-SCHED
624                                     FAN-CONTROL=
625                                     INLET
626                                     MOTOR-PLACEMENT =
627                                     IN-AIRFLOW
628                                     FAN-PLACEMENT = DRAW-THROUGH
629                                     SUPPLY-EFF=0.55575
630                                     MAX-FAN-RATIO = 1.1
631                                     MIN-FAN-RATIO = 0.3
632                                     NIGHT-CYCLE-CTRL=STAY-OFF
633                                     SUPPLY-DELTA-T = 2.117
634                                     SUPPLY-KW = 0.000685 ..
635
636 $ COIL CURVE-FIT
637 HPACCoolCapFT = CURVE-FIT
638     TYPE = BI-QUADRATIC
639     COEFFICIENTS = (0.766956,0.0107756,-0.0000414703,0.00134961,
640     -0.000261144,0.000457488) ..
641 HPACCoolCapFFF = CURVE-FIT
642     TYPE = QUADRATIC
643     COEFFICIENTS = (0.8,0.2,0) ..
644 HPACCOOLEIRFT = CURVE-FIT
645     TYPE = BI-QUADRATIC
646     COEFFICIENTS = (0.297145,0.0430933,-0.000748766,0.00597727,
647     0.000482112,-0.000956448) ..
648 HPACCOOLPLFFPLR = CURVE-FIT
649     TYPE = QUADRATIC
650     COEFFICIENTS = (0.85,0.15,0) ..
651
652 S-EQUIP   =SYSTEM-EQUIPMENT   COOL-CAP-FT = SDL-C3
653                                     COOLING-EIR = 0.242745131
654                                     COOL-EIR-FT = SDL-C13
655                                     COOL-EIR-FPLR = SDL-C18
656                                     COOL-SH-FT =SDL-C23
657                                     COIL-BF-FT = HPACCoolCapFT
658                                     COIL-BF-FCFM = HPACCoolCapFFF
659                                     COIL-BF-FPLR = HPACCOOLPLFFPLR
660                                     COIL-BF=0.19
661                                     COOL-FT-MIN= 70
662                                     HEAT-CAP-FT = SDL-C55
663                                     HEATING-EIR = 0.29751543
664                                     HEAT-EIR-FT = SDL-C60
665                                     HEAT-EIR-FPLR = SDL-C65
666                                     DEFROST-FRAC-FT = HPACCOOLEIRFT
667                                     OUTSIDE-FAN-T = 45
668                                     OUTSIDE-FAN-MODE = INTERMITTENT
669                                     COMPRESSOR-TYPE = SINGLE-SPEED
670                                     RATED-CCAP-FCFM = SDL-C78
671                                     RATED-SH-FCFM= SDL-C85
672                                     RATED-CEIR-FCFM= SDL-C93
673                                     RATED-HCAP-FCFM= SDL-C100
674                                     CRANKCASE-HEAT= 0.05
675                                     CRANKCASE-MAX-T= 39.92 ..
676
677
678 S-TERM    =SYSTEM-TERMINAL REHEAT-DELTA-T= 50
679 ..
680 SYST-1   =SYSTEM              SYSTEM-TYPE= PVAVS
681                                     SYSTEM-FANS= S-FAN
682                                     SYSTEM-TERMINAL= S-TERM
683                                     SYSTEM-EQUIPMENT= S-EQUIP
684                                     HEAT-SOURCE=
685                                     HEAT-PUMP
686
687                                     PREHEAT-SOURCE= HEAT-PUMP
688                                     RETURN-AIR-PATH= DIRECT
689                                     SIZING-OPTION =

```

```

688                                     NON-COINCIDENT
                                           ZONE-NAMES=(SPACE5-1,SPACE1-1,SPACE2-1
689                                     SPACE3-1,SPACE4-1,ATTIC)
                                           ..
690
691
692 HP-1      = PLANT-ASSIGNMENT  SYSTEM-NAMES = (SYST-1)
693                                     HP-LOOP-HEATING = FROM-SYSTEMS
694                                     HP-LOOP-COOLING = FROM-SYSTEMS
695                                     DHW-SIZE      = 40
696                                     DHW-GAL/MIN   =
                                           0.0486
697                                     DHW-SCH      = DHW-SCHED
698                                     DHW-INLET-T-SCH = DHWINLETSCH-1
699                                     DHW-SUPPLY-T  =
                                           131
700                                     DHW-TYPE    = ELECTRIC
701                                     DHW-EIR     = 1
702                                     DHW-EIR-FT  = DHWHPEIRFT
703                                     DHW-HEAT-RATE-FT = DHWHPCAPFT
704                                     DHW-EIR-FPLR = DHWGEIRFPLR
705                                     DHW-PUMP-ELEC = 0
706                                     MAX-FLUID-T = 140
707                                     MIN-FLUID-T = 50
708                                     FLUID-VOLUME = 15      ..
709
710
711
712 $===== HOURLY-REPORT FOR SYSTEM
=====
713
714 $ HOURLY-REPORT FOR SYSTEM PART
715 HRSCH-2      = SCHEDULE
716                 THRU DEC 31 (ALL) (1,24) (1) ..
717
718 S1_ZT        = REPORT-BLOCK
719                 VARIABLE-TYPE=SPACE1-1
720                 VARIABLE-LIST=(6,14)
721                 ..
722
723 S2_ZT        = REPORT-BLOCK
724                 VARIABLE-TYPE=SPACE2-1
725                 VARIABLE-LIST=(6,14)
726                 ..
727
728 S3_ZT        = REPORT-BLOCK
729                 VARIABLE-TYPE=SPACE3-1
730                 VARIABLE-LIST=(6,14) ..
731
732 S4_ZT        = REPORT-BLOCK
733                 VARIABLE-TYPE=SPACE4-1
734                 VARIABLE-LIST=(6,14) ..
735
736 S5_ZT        = REPORT-BLOCK
737                 VARIABLE-TYPE=SPACE5-1
738                 VARIABLE-LIST=(6,14)
739                 ..
740
741 SYS1         = REPORT-BLOCK
742                 VARIABLE-TYPE=SYST-1
743                 VARIABLE-LIST=(1,2) ..
744
745 PPRT1       = HOURLY-REPORT
746                 REPORT-SCHEDULE = HRSCH-2
747                 REPORT-BLOCK = (S1_ZT,S2_ZT,S3_ZT,S4_ZT,S5_ZT,SYs1) ..
748
749 $=====

```

```
749
750 END ..
751 COMPUTE SYSTEMS ..
752
753
754 INPUT PLANT ..
755
756         PLANT-REPORT SUMMARY=(ALL-SUMMARY)
757         REPORT-FREQUENCY = HOURLY
758         HOURLY-DATA-SAVE = FORMATTED ..
759
760 $===== HOURLY-REPORT FOR PLANT
761 =====
762 HRSCH-3      = SCHEDULE
763              THRU DEC 31 (ALL) (1,24) (1) ..
764
765 PLT         = REPORT-BLOCK
766             VARIABLE-TYPE=PLANT
767             VARIABLE-LIST=(3) ..
768
769 ENDU        = REPORT-BLOCK
770             VARIABLE-TYPE=END-USE
771             VARIABLE-LIST=(1,3,5,6,9)
772             ..
773
774 PFRT1       = HOURLY-REPORT
775             REPORT-SCHEDULE = HRSCH-3
776             REPORT-BLOCK = (PLT,ENDU) ..
777
778 $=====
779
780 END ..
781 COMPUTE PLANT ..
782
783
784
785 STOP ..
786
```


3 REFERENCE

- [1] Kim, C. 2020. A study of occupancy-based smart building controls in commercial buildings. Ph.D. Dissertation, Texas A&M University.
- [2] ASHRAE. (2017). Standard 90.1-2016 User's Manual. Atlanta, GA, American Society of Heating, Refrigerating, and Air-conditioning Engineers.
- [3] PNNL and U.S.DOE. (2014). Commercial Prototype Building Models. U.S. Department of Energy (DOE). Retrieved from https://www.energycodes.gov/development/commercial/prototype_models.

Appendix A: Simulation Information

Appendix A describes the detailed information to support DOE-2.1e models modified based on the U.S.DOE commercial prototype buildings for Standard 90.-2016. The tables in Appendix A provide further information for the boundary conditions (i.e., walls, roof, ground, etc.) and internal heat gains.

Table A-1 Summary of Small Office Model Construction

#	Type	Houston (2A)		Chicago (5A)	
		U-Value (Btu/hr-ft ² -F)	SHGC	U-Value (Btu/hr-ft ² -F)	SHGC
1	Roof	0.526	0.0257	0.526	0.0202
2	Ceiling	0.027	(0.027)	0.021	(0.021)
3	External wall	0.087	(0.089)	0.050	(0.051)
4	Interior wall	0.442	-	0.442	-
5	Ground floor*	0.415	(F-0.730)	0.415	(F-0.520)
6	Window**	0.52	(0.54)	0.367	(0.38)
7	Glass door**	0.52	(0.54)	0.367	(0.38)
8	Opaque door	0.370	(0.037)	0.370	-

* Note: The numbers in brackets are code-compliance for Standard 90.1-2016. U-value and SHGC were extracted from DOE-2.1e LV-C and LV-D reports. U-values included air films.

* Ground floor is slab-on-grade (unheated) both for Houston and Chicago models, which used 8" concrete slab with carpet pad. As of August 2020, DOE updated the prototype models using F-factor for underground calculations. Before then, U-value used for underground calculations. The construction of F-factor insulation can be found in Standard 90.1-2016, Table A6.3.1.

** Hypothetical window with weighted U-factor and SHGC used based on the PNNL prototype models. The weighting process is described in Thornton et al. (2011).

Table A-2 Houston (2A): Small Office Model Material Layers

#	Type	Material Layers (Outside to Inside)
1	Attic roof	Asphalt shingles, 5/8" plywood
2	Ceiling insulation	Insulation (R-35.4), 15/8" gypsum board
3	External slab 8" with carpet	7 7/8" normal-weight concrete floor, carpet pad
4	Exterior wall	1" stucco, 5/8" gypsum board, insulation (R-9), 5/8" gypsum board
5	Interior wall	1/2" gypsum board, 1/2" gypsum board
6	Exterior roof soffit	5/8" plywood
7	Window	Glass 1576, air 2 1/16", Glass 102 (U-value 0.58, SHGC 0.25)
8	Glass door	U-value 0.58, SHGC 0.25
9	Swinging door	Opaque door panel

Table A-3 Chicago (5A): Small Office Model Material Layers

#	Type	Material Layers (Outside to Inside)
1	Attic roof	Asphalt shingles, 5/8" plywood
2	Ceiling insulation	Insulation (R-45.98), 5/8" gypsum board
3	External slab 8" with carpet	7 7/8" normal-weight concrete floor, carpet pad
4	Exterior wall	1" stucco, 5/8" gypsum board, insulation (R-17.43), 5/8" gypsum board
5	Interior wall	1/2" gypsum board, 1/2" gypsum board
6	Exterior roof soffit	5/8" plywood
7	Window	Glass 8652, air 1/2", Glass 102 (U-value 0.41, SHGC 0.38)
8	Glass door	U-value 0.41, SHGC 0.38
9	Swinging door	Opaque door panel

Table A-4 Average Monthly Ground Temperature in DOE-2.1e and EnergyPlus

Month	Houston (CZ 2A, °F)	Chicago (CZ 5A, °F)	Reference
January	69.314	67.838	PNNL and U.S.DOE (2014)
February	69.224	67.604	
March	69.368	67.604	
April	69.512	37.838	
May	69.692	68.180	
June	73.634	72.050	
July	74.300	73.184	
August	74.444	73.526	
September	74.480	73.634	
October	70.448	69.944	
November	69.818	68.954	
December	69.458	68.342	

Table A-5 Internal Heat Gain Inputs in DOE-2.1e and EnergyPlus Simulation Tests

Heat sources	DOE-2.1e	EnergyPlus	Reference
Occupancy	- 450W/person	- 450W/person	ASHRAE (2017)
	- 200ft ² /person	- 200ft ² /person	
Electrical equipment	0.63 W/ft ²	0.63 W/ft ²	ASHRAE (2017)
Internal lighting	0.79 W/ft ²	0.79 W/ft ²	ASHRAE (2017)
Task lighting	Not modeled	Not modeled	N/A